

URBAN
90% FED.
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE							
				ROADWAY	LANDSCAPING	BRIDGE	BRIDGE	BRIDGE	MINOR STRUCTURES	SAFETY	
				0004 S.N.	0001 URBAN	0011 S.N. 016-1322	0011 S.N. 016-1323	0011 S.N. 016-2573	0040 S.N. 016-2014	0021 URBAN	
60500105	FILLING MANHOLES	EACH	4	4							
60500205	FILLING CATCH BASINS	EACH	4	4							
60500305	FILLING INLETS	EACH	1	1							
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	17	17							
60600605	CONCRETE CURB, TYPE B	FOOT	100	100							
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQFT	465	465							
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	1	1							
60900515	CONCRETE THRUST BLOCKS	EACH	1	1							
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2							
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2							
63500105	DELINEATORS	EACH	44	44							
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	475	475							
63700805	CONCRETE BARRIER TRANSITION	FOOT	30	30							
63700900	CONCRETE BARRIER BASE	FOOT	3101	3101							
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	950	950							
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1							
67100100	MOBILIZATION	L SUM	1	1							

FILE NAME: I-90-114 at Ohio Street\ROAD\CADD SHEETS\016F63-500.dwg

- - DENOTES SPECIALTY ITEM
- ☐ - DENOTES 100% CITY OF CHICAGO
- △ - DENOTES NON-PARTICIPATING ITEM



USER NAME: krgall
 PLOT SCALE: 2.0000' / 1" IN.
 PLOT DATE: 3/25/2013

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET
 SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	0303-474HB-R	COOK	368	11
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60F63	