CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE URBAN 90% FED. 10% STATE ROADWAY 0004 S.N.	~~LANDSCAPING~~ ~~0031~~ ~~URBAN~~	BRIDGE 0011 S.N. 016-1322	BRIDGE 0011 S.N. 016-1323	BRIDGE 0011 S.N. 016-2573	MINOR STRUCTURES 0040 S.N. 016-Z014	SAFETY 0021 URBAN
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18						
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1						
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	12492	12492						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14065	14065						
70400100	TEMPORARY CONCRETE BARRIER	FOOT	6246	6246						
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2127	2127						
70600240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	3	3						
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	9	9						
70600255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1						
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2						
70600322	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2						
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	10	10						
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	3	3						
* 72000100	SIGN PANEL - TYPE 1	SQ FT	7	7						
* 72000200	SIGN PANEL - TYPE 2	SQ FT	165	165						
* 72000300	SIGN PANEL - TYPE 3	SQ FT	93	93						
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1						

* - DENOTES SPECIALTY ITEM
- DENOTES 100% CITY OF CHICAGO
△ - DENOTES NON-PARTICIPATING ITEM

FILE NAME = 1b7808 - I94 at Ohio Stre**\CADD\CADD SHEETS\01BF63-SC00.dgn

COLLINS ENGINEERS INC

USER NAME = rgoll	DESIGNED -	REVISED -
PLOT SCALE = 2.0000 ' / in.	DRAWN -	REVISED -
PLOT DATE = 3/25/2013	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	0303-474HB-R	COOK	368	12
		CONTRACT NO. 60F63		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT