

PROPOSED PAVEMENT

LOCATION	STATION		AGG SUBGRADE 12" (SQ YD)	STAB SUBBASE 4" (SQ YD)	PCC PVT 10-1/4" JOINTED (SQ YD)	BRIDGE APPROACH PVT CONNECTOR (SQ YD)	CRC 12" (SQ YD)	AGG SHLD, TY B 8" (SQ YD)	PCC SHLD, 10- 1/4" (SQ YD)	PCC SHLD, 12" (SQ YD)	
	FROM	TO									
RAMP A	09+19.73	10+26.31	670	670	422				248		
RAMP C	103+00.00	106+01.10			535				508		
RAMP C	106+01.10	107+21.79	6659	6659		318					
RAMP C	112+18.45	113+39.17				409					
RAMP C	113+39.17	126+84.08					2378		686	2300	
RAMP C	126+84.08	127+90.43						212			
RAMP B	10+92.14	13+41.88							111		
RAMP D	08+20.00	11+06.71	624	624			40	624			
I-90/94 (WB)	117+27.29	120+67.75	486	486						486	
I-90/94 (EB)	207+03.90	221+02.35	962	962						962	
TOTAL			9400	9400	3334	727	212	837	3679	1447	

PROPOSED BARRIER WALL

LOCATION	STATION		OFFSET	CONC BAR, VAR. CROSS SECT, 42" (LF)	CONC BAR, 1F, 42" HT SPL (LF)	CONC BAR BASE (LF)	CONC BAR TRANSITION (LF)
	FROM	TO					
I-90/94 WB	11727.78	12024.64	RT		297	297	
I-90/94 WB	119+17.13	120+67.79	RT	151		151	
I-90/94 EB	219+40.64	221+02.38	LT	162		162	
I-90/94 EB	219+40.64	221+02.38	RT	162		162	
I-90/94 EB	219+64.21	222+26.42	RT		285	285	
RAMP C	103+00.00	106+90.75	RT		391	391	
	103+00.00	106+90.75	LT		391	391	
	113+14.95	113+47.04	LT		32	32	
	113+14.95	115+75.22	RT		260	260	
	119+20.00	120+00.00	LT		80	80	15
	123+60.00	124+00.00	LT		40	40	
	123+60.00	124+00.00	LT		40	40	
	16+20.00	17+87.77	RT		168	168	
	16+20.00	17+87.77	LT		168	168	
RAMP D	09+18.08	11+06.71	RT		189	189	15
RAMP D	07+93.59	10+58.12	LT		285	285	
TOTAL				474	2625	3100	30

PROPOSED BARRIER WALL

LOCATION	STATION		OFFSET	IMP ATT T3 (NON- REDIRECTIVE)	TR BAR TRMT1 SPL TAN (EACH)	TR BAR TRM T6 (EACH)	GUARDRAIL MARKERS (EACH)	TERM MARK DIRECT APPLIED (EACH)
	FROM	TO						
RAMP C	118+39.88		LT			1		
RAMP C	118+61.00		LT		1		4	1
RAMP D	07+93.59		LT	1			4	
RAMP D	08+46.00		RT		1			1
RAMP D	08+88.00		RT			1		
TOTAL				1	2	2	8	2

FILE NAME = I:\7000 - 194 at Ohio Street\CADD\CADD_SHEETS\160663-SCHEDULES.dgn



USER NAME = rge11	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 3/25/2013	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

I-90/94 AT OHIO STREET SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE. 90/94	SECTION 0303-474HB-R	COUNTY COOK	TOTAL SHEETS 368	SHEET NO. 32
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60F63	