

EARTHWORK SCHEDULE

STA. FROM	TO STA.	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
RAMP C						
113+50.00	114+00.00	0.97	37.13	0.83	200.29	-199.46
114+00.00	114+50.00	0.94	30.31	0.79	165.80	-165.01
114+50.00	115+00.00	0.60	25.75	0.51	136.73	-136.22
115+00.00	115+50.00	0.26	25.64	0.22	127.24	-127.02
115+50.00	116+00.00	14.56	28.93	12.38	109.79	-97.41
116+00.00	116+50.00	31.36	33.08	26.65	94.09	-67.43
116+50.00	117+00.00	24.62	34.87	20.93	85.53	-64.60
117+00.00	117+50.00	21.68	48.06	18.42	98.01	-79.58
117+50.00	118+00.00	42.16	63.80	35.84	113.11	-77.27
118+00.00	118+50.00	78.80	71.19	66.98	106.51	-39.53
118+50.00	119+00.00	110.16	78.33	93.63	109.42	-15.79
119+00.00	119+50.00	138.23	79.10	117.50	109.99	7.51
119+50.00	120+00.00	172.00	110.77	146.20	73.57	72.62
120+00.00	120+50.00	208.97	148.96	177.63	79.19	98.44
120+50.00	121+00.00	287.30	150.24	244.21	92.54	151.67
121+00.00	121+50.00	437.10	145.83	371.54	49.87	321.67
121+50.00	122+00.00	617.43	143.31	524.81	17.91	506.90
122+00.00	122+50.00	734.95	139.11	624.71	3.25	621.47
122+50.00	123+00.00	760.19	133.19	646.17	1.62	644.54
123+00.00	123+50.00	723.16	126.83	614.68	1.64	613.04
123+50.00	124+00.00	652.09	133.71	554.27	3.70	550.57
124+00.00	124+50.00	485.96	130.42	413.06	6.01	407.06
124+50.00	125+00.00	300.29	123.77	255.25	6.39	248.86
125+00.00	125+50.00	181.08	97.01	153.92	3.80	150.12
125+50.00	126+00.00	106.06	61.71	90.16	1.17	88.98
126+00.00	126+50.00	71.15	57.09	60.48	1.08	59.40
126+50.00	127+00.00	37.94	49.47	32.25	0.65	31.60
127+00.00	127+50.00	22.75	43.74	19.34	0.40	18.94
TOTAL		6262.76	2351.34	5323.35	1799.26	3524.08

STA. FROM	TO STA.	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
RAMP B						
11+00.00	11+50.00	29.54	28.68	25.11	0.09	25.02
11+50.00	12+00.00	19.64	23.47	16.69	0.10	16.60
12+00.00	12+50.00	20.14	25.69	17.12	1.00	16.11
12+50.00	13+00.00	46.27	44.00	39.33	3.22	36.11
TOTAL		115.59	121.84	98.25	4.41	93.84

STA. FROM	TO STA.	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
RAMP D						
8+00.00	8+50.00	79.62	21.57	67.67	84.04	-16.36
8+50.00	9+00.00	83.75	11.76	71.19	109.21	-38.02
9+00.00	9+50.00	86.53	6.84	73.55	67.91	5.64
9+50.00	10+00.00	94.65	4.77	80.45	57.11	23.35
10+00.00	10+50.00	124.35	15.70	105.70	75.44	30.26
10+50.00	11+00.00	116.56	20.93	99.08	68.95	30.12
TOTAL		585.45	81.58	497.64	462.65	34.99

STA. FROM	TO STA.	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
RAMP C		6262.76	2351.34	5323.35	1799.26	3524.08
RAMP B		115.59	121.84	98.25	4.41	93.84
RAMP D		585.45	81.58	497.64	462.65	34.99
STAGE 1		962.20	526.44	817.87	83.76	734.11
STAGE 2		896.57	310.00	762.09	34.25	727.83
STAGE 3		64.91	324.96	55.17	1718.97	-1663.80
GRAND TOTAL		8887.49	3716.16	7554.36	4103.31	3451.05

FILE NAME = I:\7000 - 194 at Ohio Street\CADD\CADD\_SHEET\SD160663-SCHEDULES.dgn



USER NAME = rge11  
 PLOT SCALE = 2.0000' / 1" =  
 PLOT DATE = 3/25/2013

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET  
 SCHEDULE OF QUANTITIES  
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	0303-474HB-R	COOK	368	36
CONTRACT NO. 60F63				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				