SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY 0005	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	32	32	
20400800	FURNISHED EXCAVATION	CU YD	60	60	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	714	714	
21400100	GRADING AND SHAPING DITCHES	FOOT	365	365	
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	12	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12	12	
25100630	EROSION CONTROL BLANKET	SQ YD	714	714	
25200110	SODDING, SALT TOLERANT	SQ YD	81	81	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26	
40600300	AGGREGATE (PRIME COAT)	TON	155	155	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,050	1,050	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	203	203	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,310	2,310	
42001300	PROTECTIVE COAT	SQ YD	35	35	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	25,005	25,005	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	480	480	
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	115	115	
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	115	115	
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	15	15	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	760	760	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
63200310	GUARDRAIL REMOVAL	FOOT	50	50	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,709	2,709	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	790	790	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	32,415	32,415	

35

	CODE NO.	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY 0005	
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,933	1,933	
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	455	455	
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	852	852	
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	787	787	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	15,292	15,292	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	395	395	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16,207	16,207	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,933	1,933	
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	228	228	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	426	426	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	394	394	
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	218	218	
*	78200420	GUARDRAIL MARKERS, TYPE B	EACH	4	4	
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	214	214	
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,429	1,429	
	X2020110	GRADING AND SHAPING SHOULDERS	UNIT	95	95	
	X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	150	150	
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4	4	
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6	6	
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8	

21

* SPECIALTY ITEMS

*Specialty Items

FILE NAME = C:\pwworking\stantec\d0406\sheets\d0406L07-03-summary.dgn

Stantec

USER NAME = dpierson2	DESIGNED - MRN	REVISED -
	DRAWN - STANTEC	REVISED -
PLOT SCALE = 50.00 ' / IN.	CHECKED - TMH	REVISED -
PLOT DATE = 12/11/2012	DATE - 12/11/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 176 ROADWAY RESURFACING
SUMMARY OF QUANTITIES

SCALE:50.00 ' / IN. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	145X-RS	McHENRY	20	3

CONTRACT NO. 60L07

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT