


90% FED. / 10% STATE

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY	TIFFANY RD TRAFFIC SIGNAL	INTERCONNECT	EMERGENCY VEHICLE PRE-EMPTION 100% VILLAGE
				0004	0021	0021	0021
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	711	711			
42001300	PROTECTIVE COAT	SO YD	1716	1716			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	42	42			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	9227	9227			
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SO FT	953	953			
42400800	DETECTABLE WARNINGS	SOFT	63	63			
44000100	PAVEMENT REMOVAL	SO YD	220	220			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	5628	5628			
44000200	DRIVEWAY PAVEMENT REMOVAL	SOYD	686	686			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1491.5	1491.5			
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	195	195			
44004250	PAVED SHOULDER REMOVAL	SO YD	965	965			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	180	180			
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	75	75			
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	206	206			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	48	48			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	330	330			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	166	166			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	360	360			
55100300	STORM SEWER REMOVAL 8"	FOOT	45	45			
55100500	STORM SEWER REMOVAL 12"	FOOT	585	585			
55100900	STORM SEWER REMOVAL 18"	FOOT	157	157			
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1			
60107600	PIPE UNDERDRAINS 4"	FOOT	508	508			
60200405	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 4 FRAME AND GRATE	EACH	9	9			
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1			
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	5	5			
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2	2			

\* SPECIALTY ITEM

FILE NAME : P:\2011\ME11007\_Ver.Ver\_PNT\CADD\W002\_IL173.et.TIFF\_Rd\Shcs\03-DIG\28-ent-S00.dgn  
 PLOT SCALE : 2.0000 / IN.  
 USER NAME : Millennia Professional Services



200 225D Street, Suite 216, Lombard, IL 60148  
 630.785.8118 voice, 630.839.2566 fax  
 www.mps-ll.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED	CJD	REVISED	
DRAWN	CJD	REVISED	
CHECKED	TVN	REVISED	
DATE	2/7/2013	REVISED	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 173**  
**AT TIFFANY ROAD**

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	134-N-1	LAKE	62	4
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 60L28	

SCALE: SHEET NO. 2 OF 6 SHEETS STA. TO STA.

P:\2011\ME11007\_Ver.Ver\_PNT\CADD\W002\_IL173.et.TIFF\_Rd\Shcs\03-DIG\28-ent-S00.dgn