

**SUMMARY OF QUANTITIES**

90% FED. / 10% STATE

**CONSTRUCTION TYPE CODE**

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY 0004	TIFFANY RD TRAFFIC SIGNAL 0021	INTERCONNECT 0021	EMERGENCY VEHICLE PRE-EMPTION 100% VILLAGE 0021
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	5	5			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	2	2			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1	1			
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1	1			
60234200	INLETS, TYPE A, TYPE I FRAME, OPEN LID	EACH	1	1			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7			
60500040	REMOVING MANHOLES	EACH	1	1			
60500050	REMOVING CATCH BASINS	EACH	1	1			
60500060	REMOVING INLETS	EACH	4	4			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	1.7	1.7			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1216	1216			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1747	1747			
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	174	174			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	413	413			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	2	2			
63200310	GUARDRAIL REMOVAL	FOOT	536	536			
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	3000	3000			
• 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
• 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5			
67100100	MOBILIZATION	L SUM	1	1			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	5	5			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1664	1664			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220	220			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10838	10838			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1832	1832			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	282	282			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	226	226			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	9244	9244			

P:\2011\ME11807\_Ver\_Ver\_Phil\CAD\W003\_IL173.ctb, Trf, Rd, Gha 03-0168L28-shr-500.dgn  
 08/08/11 10:58 AM  
 Phil  
 Millennium Professional Services

29

• SPECIALTY ITEM

Rev.



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.8114 voice, 630.839.3566 fax  
 www.mps-ill.com

DESIGNED	CJD	REVISED	
DRAWN	CJD	REVISED	
CHECKED	TYN	REVISED	
DATE	2/7/2013	REVISED	

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 173  
 AT TIFFANY ROAD**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	134-N-1	LAKE	62	5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60L28	

P:\2011\ME11807\_Ver\_Ver\_Phil\CAD\W003\_IL173.ctb, Trf, Rd, Gha 03-0168L28-shr-500.dgn