

SUMMARY OF QUANTITIES

URBAN


CONSTRUCTION TYPE CODE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY 0004	TIFFANY RD TRAFFIC SIGNAL 0021	INTERCONNECT 0021	EMERGENCY VEHICLE PRE-EMPTION 100% VILLAGE 0021
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	72	72			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	277	277			
72000100	SIGN PANEL - TYPE 1	SO FT	25	25			
72000200	SIGN PANEL - TYPE 2	SO FT	57.5		57.5		
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1			
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	3	3			
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1			
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2			
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	27	27			
73000100	WOOD SIGN SUPPORT	FOOT	30	30			
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	364	364			
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6464	6464			
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1307	1307			
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	141	141			
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	113	113			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	147	147			
78300100	PAVEMENT MARKING REMOVAL	SO FT	1771	1771			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	113	113			
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1		
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1572		625	947	
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	41		41		
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	55		55		
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	251		251		
81400100	HANDHOLE	EACH	9		6	3	
81400200	HEAVY-DUTY HANDHOLE	EACH	2		2		
81400300	DOUBLE HANDHOLE	EACH	1		1		
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1	
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1		

FILE NAME = P:\2011\ME11007_Ver_Ver_PN1\CAD01\003_IL173.ctb; Title: 80500020-0180L28.sht; S00.dgn
 PLOT SCALE = 2.0000 / 1 IN.
 User: Millennium Professional Services

29

• SPECIALTY ITEM



249 22ND Street, Suite 216, Lombard, IL 60148
 630.785.8118 voice, 630.839.2566 fax
 www.mps-ill.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 2/7/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 173
AT TIFFANY ROAD

SUMMARY OF QUANTITIES

F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	134-N-1	LAKE	62	6
CONTRACT NO. 60L28				

SCALE: SHEET NO. 4 OF 6 SHEETS STA. TO STA.