


NOTES

1. ALL PAVEMENT MARKINGS ARE THERMOPLASTIC.
2. THE CONSTRUCTOR SHALL PLACE PROPOSED PAVEMENT MARKINGS IN ACCORDANCE WITH DISTRICT 1 TYPICAL PAVEMENT MARKINGS DETAIL (TC-13).
3. REFER TO DISTRICT 1 RAISED REFLECTIVE PAVEMENT MARKERS (TC-11) FOR ADDITIONAL INFORMATION.
4. SALVAGE TIFFANY RD SIGN AND RELOCATE TO NEW WOOD POST. QUANTITY IS INCIDENTAL.

LANDSCAPING LEGEND



PAVEMENT MARKING LEGEND (SEE NOTE 1)

- | | |
|--|--|
| ① 4" WHITE LANE LINE (30' SKIP 10' DASH) | ⑥ 12" YELLOW LINE (75' C-C OR MIN 5 EVENLY SPACED) |
| ② 4" WHITE SOLID LINE | ⑦ 24" WHITE STOP BAR |
| ③ 4" DOUBLE YELLOW | ⑧ LETTERS AND SYMBOLS (TYP) |
| ④ 6" WHITE LINE (6' SKIP 2' DASH) | ⑨ RAISED REFLECTIVE PAVEMENT MARKER (SEE NOTE 3) |
| ⑤ 6" WHITE LINE | ⑩ 6" WHITE LINE (9' SKIP 2' DASH) |

FILE NAME : P:\2011\ME11007_Ver-Var-PhII\CA00\W003_IL173.st.Tiff.Rd\Shs\DI60L28-shr.pmk.Tiff.dgn
 USER : ME11007
 MILLENNIA PROFESSIONAL SERVICES



200 22ND Street, Suite 214, Lombard, IL 60148
 630.705.0110 voice, 630.839.3566 fax
 www.mps-il.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 2/4/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 173 AT TIFFANY ROAD		PAVEMENT MARKING PLAN TIFFANY ROAD	
SCALE: 1"=50'	SHEET NO. 2 OF 2 SHEETS	STA. 11+00.00	TO STA. 16+34.00

F.A.P. RTE. 303	SECTION 134-N-1	COUNTY LAKE	TOTAL SHEETS 62	SHEET NO. 26
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60L28	

P:\2011\ME11007_Ver-Var-PhII\CA00\W003_IL173.st.Tiff.Rd\Shs\DI60L28-shr.pmk.Tiff.dgn