

100% STATE

SUMMARY OF QUANTITIES				CONSTR. TYPE CODE	
CODE	ITEM DESCRIPTION	UNIT	QUANTITY	ROADWAY	STRUCTURE
				0004 URBAN	0014 URBAN
X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	160	160	
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKINGS 5"	FOOT	310	310	
* X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LUMINAIRES	L SUM	1		1
Z0001700	APPROACH SLAB REPAIRS (FULL DEPTH)	SQ YD	1		1
Z0001800	APPROACH SLAB REPAIRS (PARTIAL DEPTH)	SQ YD	3		3
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	12		12
Z0001905	STRUCTURAL STEEL REPAIR	POUND	430		430
Z0006012	BRIDGE DECK LATEX CONCRETE OVERLAY, 2-1/4"	SQ YD	1063		1063
Z0012130	BRIDGE DECK SCARIFICATION, 3/4"	SQ YD	1063		1063
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	294		294
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	28		28
Z0041895	POLYMER CONCRETE	CU FT	5.8	5.8	
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	2		2

* SPECIALTY ITEMS

I:\BL132\181\Adas-1\Posendon\0005\6718\6718.dwg - Bridge Over Top I11\0000\Structural Drawings\000 Sheets\022\0018\018M97.sht:50.dgn

FILE NAME :	USER NAME : j.schneider	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES STRUCTURE NO. 022-0090		F.A.I. RTE. 290	SECTION 22-3H8-1	COUNTY DuPAGE	TOTAL SHEETS 37	SHEET NO. 5	
	PLOT SCALE : 2.0000 ' / 1"	DRAWN - DR	REVISED -				SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 60M97			
	PLOT DATE : 12/6/2012	CHECKED - JMH	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE - JANUARY, 2013	REVISED -									