



INSTALL NEW TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL), TANGENT SEE NOTE 2

NOTE 2: EXISTING TERMINAL SECTION TO BE REPLACED WITH NEW TYPE 1 (SPECIAL), TANGENT WITH 50' LENGTH. SEE STANDARDS 630301 AND DISTRICT DETAIL BD-34

ADDITIONAL PAY ITEMS WITH QUANTITY ESTIMATED IN THIS AREA INCLUDE:

- REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL
- FURNISHED EXCAVATION
- TOPSOIL FURNISH AND PLACE, 4"
- SEEDING, CLASS 2A
- NITROGEN FERTILIZER NUTRIENT
- POTASSIUM FERTILIZER NUTRIENT
- EROSION CONTROL BLANKET
- AGGREGATE SHOULDERS, TYPE B - 6"
- GUARDRAIL REMOVAL

HMA SURF REM. 2 1/4"  
1 1/2" HMA SC "D" N70  
3/4" P LB MM IL-4.75 N50

GRADING & SHAPING  
DITCHES  
(APPROXIMATE LIMITS)  
TOPSOIL FURNISH AND PLACE, 4"  
SEEDING, CLASS 2A

FILE NAME = G:\p\c\sect\2102155\_0050\CADDD\Cvt1\Sh\1\0160N54-17-RDWY-012.dgn



USER NAME = dpieniazek	DESIGNED - DJB	REVISED -
	DRAWN - STANTEC	REVISED -
PLOT SCALE = 50.00' / IN.	CHECKED - TMH	REVISED -
PLOT DATE = 12/12/2012	DATE - 12/12/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 120 ROADWAY RESURFACING  
EXISTING AND PROPOSED ROADWAY AND PAVEMENT MARKING PLAN**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
333	15-RS-12	MCHENRY	33	17
			CONTRACT NO. 60N54	
ILLINOIS FED. AID PROJECT				