

URBAN
100% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0014 STRUCTURE	0004 ROADWAY
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6205		6205
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2036.0		2036.0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	226		226
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	869		869
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	106		106
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12		12
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8		8
78200530	BARRIER WALL MARKERS, TYPE C	EACH	147		147
78300100	PAVEMENT MARKING REMOVAL	SO FT	4666		4666
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	142		142
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1
A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2+1/2" CALIPER, BALLED AND BURLAPPED	EACH	9		9
X0326394	FLOOR DRAINS TO BE CLEANED	EACH	8	8	
X0326766	CLEAN & RESEAL RELIEF JOINT	FOOT	52	52	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	707	707	
X5210025	ELASTOMERIC BEARING ASSEMBLY, TYPE II (SPECIAL)	EACH	40	40	
X6060714	CONCRETE MEDIAN (SPECIAL)	SO FT	2895		2895
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	12173		12173
X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	1353		1353
Z0001500	APPROACH SLAB REMOVAL & REPLACEMENT	SO YD	30	30	
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	40	40	
Z0006014	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SO YD	1155	1155	

URBAN
100% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0014 STRUCTURE	0004 ROADWAY
Z0012144	BRIDGE DECK SCARIFICATION, 2 1/2"	SO YD	1155	1155	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	259	259	
Z0015802	PLUG EXISTING DECK DRAINS	EACH	16	16	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	3	3	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1		1
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	154		154
Z0062456	TEMPORARY PAVEMENT	SO YD	1370		1370
Z0064600	SELECTIVE CLEARING	ACRES	0.4		0.4
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	3	3	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1
X5538600	STORM SEWERS TO BE CLEANED 36"	FOOT	500		500
X0327577	PROTECT AND MAINTAIN EXISTING UNDERPASS LUMINAIRE	L SUM	1		1

!! DENOTES SPECIALTY ITEM



USER NAME - Plotted by Fred 576	DESIGNED - SEW	REVISED -
DRAWN - RK	CHECKED - SEW	REVISED -
PLOT SCALE - 2,0000' / IN.	DATE - 11/2011	REVISED -
PLOT DATE - 12/5/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 56 (BUTTERFIELD RD.) OVER IL 38 (ROOSEVELT RD.)

SCALE: N/A SHEET NO. 2 OF 2 SHEETS

F.A.P. RTE. 347	SECTION JR-HB-1-1	COUNTY DUPAGE	TOTAL SHEETS 30	SHEET NO. 4
CONTRACT NO. 60N77			ILLINOIS FED. AID PROJECT	

Rev.