

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITY	URBAN	
				0014	
				100% STATE	
* 81800320	AERIAL CABLE, 3-1/2 NO. 4 WITH MESSENGER WIRE	FOOT	900	900	
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	2	2	
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15 FT MAST ARM	EACH	2	2	
* 83057535	LIGHT POLE, WOOD, 100 FOOT, CLASS 2, WITH 15 FT MAST ARM	EACH	2	2	
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	4	4	
	87900200	DRILL EXISTING HANDHOLE	EACH	1	1
	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2	2
	X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	376	376
	X5030530	FLOOR DRAIN EXTENSION	EACH	42	42
	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
	X7030030	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	2,610	2,610
	X7030055	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	24	24
* X8210190	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT (INSTALL ONLY)	EACH	2	2	
* X8250230	PHOTOCELL	EACH	2	2	

SPECIALTY ITEM *

FILE NAME: D:\6063\shl-500.dgn
 PLOT DATE: 1/7/2013
 PLOT SCALE: 1/8" = 1' IN.



CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-8274

DESIGNED - S.J.P.
 DRAWN - A.C.S.
 CHECKED - M.P.
 DATE - OCTOBER 9, 2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL. RTE. 53

SCALE: NONE SHEET NO. 3 OF 4 SHEETS STA. 114+15 TO STA. 123+02

F.A.P. RTE. 846	SECTION K-29-A-BR-1	COUNTY WILL	TOTAL SHEETS 55	SHEET NO. 5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 6063	