



**PARTIAL DECK PLAN**

**LEGEND:**

-  Deck Slab Repair (Partial) (59 Sq. Yds. total)
-  Expansion Joint Reconstruction

*Notes:*  
 Deck Slab Repair (partial) areas and quantities shown are for information only. See Special Provisions.  
 For Expansion Joint Reconstruction Details, see Sht's. S11 thru S16.  
 Proposed overlay to be tapered at existing floor drains, for details see Sht. S10.  
 Raise the existing grate on the existing drainage scuppers by adding a fabricated adjusting ring, for details see Sht. S10.

FILE NAME = I:\102918\_11\_53 (baltimore)\structural\cadd sheets\1106163-07-dk\_repair-IV.dgn



USER NAME = IDOT	DESIGNED - J.C.N./B.N.S.	REVISED -
PLOT SCALE = 100.000000' / IN.	CHECKED - B.N.S./J.C.N.	REVISED -
PLOT DATE = 1/7/2013	DRAWN - F.M.	REVISED -
	DATE - OCTOBER 9, 2012	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**DECK PLAN REPAIRS-IV  
 STRUCTURE NO. 099-0272**

SHEET NO. S7 OF S19 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
846	K-29-A-BR-1	WILL	55	36
CONTRACT NO. 60R63			ILLINOIS FED. AID PROJECT	