

21

100% STATE

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0005					
				RESURFACING					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	28					
40600300	AGGREGATE (PRIME COAT)	TON	132	132					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,519	2,519					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	231	231					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5,695	5,695					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	65,553	65,553					
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	967	967					
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	270	270					
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	1,235	1,235					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3,860	3,860					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					

• SPECIALTY ITEM

FILE NAME: C:\projects\ILLINOIS Department of Transportation\PTB 182 - Item 7 - Various Vertical Work Order No. 3 - IL 47 Plato Road Sheets\0181815-11-1300.dgn
 SHT.PLAN

USER NAME: smiller	DESIGNED - MTM	REVISED -
PLOT SCALE: 100.0000 / 1 in.	DRAWN - MTM	REVISED -
PLOT DATE: 1/25/2013	CHECKED - BA	REVISED -
	DATE - 2/1/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 47 PLATO RD. TO U.S. 20
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 326	SECTION 106X-R5-7	COUNTY KANE	TOTAL SHEETS 20	SHEET NO. 3
				CONTRACT NO. 60V64
ILLINOIS FED. AID PROJECT				