D160W48-03-04-S00.dgn 3:32:42 PM 4/9/2013

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				100% STATE					
				ROADWAY					
				0021					
				URBAN					
20200100	EARTH EXCAVATION	CU YD	186						
25000310	SEEDING, CLASS 4	ACRE	0.1						
25100630	EROSION CONTROL BLANKET	SQ YD	209						
28000400	PERIMETER EROSION BARRIER	FOOT	20						
31101810	SUBBASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	209						
31200110	STABILIZED SUBBASE 6"	SQ YD	209						
48300820	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	209						
67100100	MOBILIZATION	L SUM	1						
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	675						
70400100	TEMPORARY CONCRETE BARRIER	FOOT	675						
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1						
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	360						
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	320						
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	108						

*Specialty Items

ABNA

USER NAME = tpaolucchi	DESIGNED - TP, GA	REVISED -
	DRAWN - MR	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - TP	REVISED -
PLOT DATE = 4/9/2013	DATE - 04/01/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 1 OF 2 SHEETS | STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	0203.1(R-2&3)1	COOK	10	3

CONTRACT NO. 60W48

ILLINOIS FED. AID PROJECT