SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE HBP FUNDS 80% FED 20% LOCAL			
				ROADWAY 0004 URBAN	BRIDGE 0014 URBAN	TRAFFIC SIGNALS 0021 URBAN	LIGHTING 0021 URBAN
50300255	CONCRETE SUPERSTRUCTURE	CU YD	546.3		546.3		
50300260	BRIDGE DECK GROOVING	SQ YD	768		768		
50300280	CONCRETE ENCASEMENT	CU YD	2.2		2.2		
50300300	PROTECTIVE COAT	SQ YD	1,473		1,473		
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	167.5		167.5		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	120,250		120,250		
50800515	BAR SPLICERS	EACH	773		773		
* 50901720	BICYCLE RAILING	FOOT	408		408		
* 50901750	PARAPET RAILING	FOOT	340		340		
51201400	FURNISHING STEEL PILES HP10X42	FOOT	911		911		
51202305	DRIVING PILES	FOOT	911		911		
51203400	TEST PILE STEEL HP10X42	EACH	4		4		
51500100	NAME PLATES	EACH	1		1		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	8	8			

* SPECIALTY ITEM