

**SIGNING SCHEDULE**

SIGN INFORMATION						NEW SIGN PANELS	NEW SIGN PANELS	METAL POST	CAST IRON BASE	
STATION	LOCATION	OFFSET		SIGN NUMBER	WIDTH (FT)	HEIGHT (FT)	(72000100)	(72000200)	(72800100)	(73100100)
		LT	RT				SIGN PANEL TYPE 1 (SQ. FT.)	SIGN PANEL TYPE 2 (SQ. FT.)	TELESCOPING STEEL SIGN SUPPORT (L.F.)	BASE FOR TELESCOPING SIGN SUPPORT (EACH)
103+00.00	IL ROUTE 47		RT	8	7.00	2.50		17.50	29.0	2
105+79.92	IL ROUTE 47		RT	4	3.00	3.00	9.00		16.0	1
105+79.92	IL ROUTE 47		RT	9	2.00	1.00	2.00			
107+32.93	IL ROUTE 47		LT	3	2.50	3.00			15.0	1
109+54.06	IL ROUTE 47		LT	1	2.00	2.50			14.5	1
109+54.06	IL ROUTE 47		LT	3	2.00	2.50				
110+84.21	IL ROUTE 47		RT	1	2.00	2.50			14.5	1
110+84.21	IL ROUTE 47		RT	3	2.00	2.50				
113+08.45	IL ROUTE 47		RT	3	2.50	3.00			15.0	1
114+58.00	IL ROUTE 47		LT	4	3.00	3.00			16.0	1
114+58.00	IL ROUTE 47		LT	9	2.00	1.00	2.00			
118+02.06	IL ROUTE 47		LT	7	7.00	2.50		17.50	29.0	2
13+72.00	OLD OAKS RD		RT	5	2.50	2.50	6.25		14.5	1
17+72.99	WAUBONSEE DR		RT	2	2.50	3.00	7.50			
18+59.95	WAUBONSEE DR		LT	6	2.50	2.50	6.25			
	MAST ARM MOUNTED		IL RTE 47				6.75			
	MAST ARM MOUNTED		IL RTE 47				6.75			
	MAST ARM MOUNTED		OLD OAKS RD				8.25			
	MAST ARM MOUNTED		WAUBONSEE DR							
<b>TOTAL</b>						<b>99</b>	<b>45</b>	<b>164</b>	<b>11</b>	

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)				
TREE #	STATION	OFFSET	UNIT	
1882	13+49.64	35.60	RT	6
1783	13+73.89	40.56	RT	9
1784	13+95.85	43.28	RT	9
1788	14+06.93	35.19	RT	7
1789	14+32.52	46.53	RT	8
1790	14+34.24	36.30	RT	11
1790A	14+34.24	36.30	RT	8
1890	14+03.30	13.34	RT	10
10	18+14.41	-22.01	LT	10
<b>TOTAL</b>				<b>78</b>

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)				
TREE #	STATION	OFFSET	UNIT	
1888	14+06.93	35.19	RT	17
<b>TOTAL</b>				<b>17</b>

IL ROUTE 47 EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUITABLE EARTH EXCAVATION (CUT)	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO	STATION	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD
104+30.00	TO	105+00.00	4	16	12	5	7
105+00.00	TO	106+00.00	11	48	36	28	8
106+00.00	TO	107+00.00	17	61	46	26	19
107+00.00	TO	108+00.00	21	80	60	9	51
108+00.00	TO	109+00.00	36	102	76	20	57
109+00.00	TO	109+09.00	5	10	8	3	5
109+09.00	TO	109+50.00	49	53	39	195	-155
109+50.00	TO	109+85.00	41	45	34	166	-132
INTERSECTION							
110+55.00	TO	111+00.00	47	55	41	32	9
111+00.00	TO	112+00.00	64	111	84	36	48
112+00.00	TO	113+00.00	23	100	75	0	75
113+00.00	TO	114+00.00	20	95	72	0	72
114+00.00	TO	115+00.00	18	103	78	0	78
115+00.00	TO	116+00.00	16	110	83	0	83
116+00.00	TO	116+70.00	5	37	28	0	28
<b>TOTALS =</b>			<b>377</b>	<b>1,027</b>	<b>770</b>	<b>520</b>	<b>250</b>

OLD OAKS ROAD EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUITABLE EARTH EXCAVATION (CUT)	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO	STATION	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD
11+17.65	TO	11+25.00	2	7	5	0	5
11+25.00	TO	11+50.00	7	21	16	0	16
11+50.00	TO	11+75.00	6	19	14	0	14
11+75.00	TO	12+00.00	6	19	14	0	14
12+00.00	TO	12+25.00	7	22	16	0	16
12+25.00	TO	12+50.00	8	26	20	0	20
12+50.00	TO	12+75.00	9	37	28	0	28
12+75.00	TO	13+00.00	10	53	39	0	39
13+00.00	TO	13+25.00	10	65	49	0	49
13+25.00	TO	13+50.00	10	70	53	0	53
13+50.00	TO	13+75.00	10	72	54	0	54
13+75.00	TO	14+00.00	11	70	53	2	51
14+00.00	TO	14+25.00	14	62	47	5	42
14+25.00	TO	14+50.00	13	54	41	7	34
14+50.00	TO	15+07.84	26	117	88	19	69
<b>TOTALS =</b>			<b>151</b>	<b>715</b>	<b>536</b>	<b>33</b>	<b>504</b>

WAUBONSEE DRIVE EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUITABLE EARTH EXCAVATION (CUT)	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO	STATION	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD
16+46.03	TO	16+75.00	10	18	14	2	11
16+75.00	TO	17+00.00	8	13	10	2	8
17+00.00	TO	17+25.00	8	14	10	2	8
17+25.00	TO	17+50.00	7	11	8	2	7
17+50.00	TO	17+75.00	8	14	10	1	10
17+75.00	TO	18+00.00	10	17	13	0	13
18+00.00	TO	18+25.00	10	18	14	0	14
18+25.00	TO	18+50.00	12	22	17	0	17
18+50.00	TO	18+75.00	11	25	19	0	19
18+75.00	TO	19+00.00	12	34	25	0	25
19+00.00	TO	19+25.00	14	47	36	0	35
19+25.00	TO	19+50.00	13	46	34	1	33
19+50.00	TO	19+75.00	11	29	21	3	19
19+75.00	TO	20+00.00	9	15	11	2	9
20+00.00	TO	20+16.27	5	7	5	0	5
<b>TOTALS =</b>			<b>150</b>	<b>330</b>	<b>248</b>	<b>16</b>	<b>232</b>

EARTHWORK SUMMARY TABLE		
ITEM	UNIT	TOTAL
<b>IL ROUTE 47 WIDENING</b>		
EARTH EXCAVATION (20200100)	CU YD	1,027
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	377
FURNISHED EXCAVATION (20400800)	CU YD	0
<b>OLD OAKS ROAD RECONSTRUCTION</b>		
EARTH EXCAVATION (20200100)	CU YD	715
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	151
FURNISHED EXCAVATION (20400800)	CU YD	0
<b>WAUBONSEE DRIVE WIDENING AND RESURFACING</b>		
EARTH EXCAVATION (20200100)	CU YD	330
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	150
FURNISHED EXCAVATION (20400800)	CU YD	0
<b>GRAND TOTALS</b>		
EARTH EXCAVATION (20200100)	CU YD	<b>2,075</b>
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	<b>680</b>
FURNISHED EXCAVATION (20400800)	CU YD	<b>0</b>