

# SUMMARY OF QUANTITIES

URBAN  
HSIP  
0021

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	90% FED 10% STATE
28000500	INLET AND PIPE PROTECTION	EACH	6	6
30300011	AGGREGATE SUBGRADE IMPROVEMENT	TON	28,453	28,453
35101400	AGGREGATE BASE COURSE, TYPE B	TON	156	156
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	88,088.8	88,088.8
40600300	AGGREGATE (PRIME COAT)	TON	55.4	55.4
40600535	LEVELING BINDER (HAND METHOD), N70	TON	25	25
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	879	879
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,838	1,838
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	2,049	2,049
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	380	380
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	120	120
40600990	TEMPORARY RAMP	SQ YD	828	828
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	6,455	6,455
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,591	2,591

\* SPECIALTY ITEM

△ NON PARTICIPATING 100% STATE

FILE NAME :	USER NAME : dssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\p\work\p\idos\dssdd\48275077\020621\1-gh-500.dgn	1-gh-500.dgn	DRAWN -	REVISED -			517	IR	BOONE	126	4
Default	PLOT SCALE : 100.0000 1/16"	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
	PLOT DATE : Tue Mar 19 06:27:20 2013	DATE -	REVISED -							
ILLINOIS FED. AID PROJECT										CONTRACT NO. 64G97

Rev.