

# SCHEDULE OF QUANTITIES

63700153 CONCRETE BARRIER, VARIABLE CROSS-SECTION, 32" HEIGHT

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
447	Sta 314+28 - 318+75 Concrete Barrier Transition Taper
2,584	Sta 318+75 - 344+59
141	Sta 344+59 - 346+00 Concrete Barrier Transition Taper
<u>1,417</u>	Sta 346+00 - 360+17
4,589	TOTAL

63700900 CONCRETE BARRIER BASE

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
447	Sta 314+28 - 318+75 Concrete Barrier Transition Taper
2,584	Sta 318+75 - 344+59
141	Sta 344+59 - 346+00 Concrete Barrier Transition Taper
<u>1,417</u>	Sta 346+00 - 360+17
4,589	TOTAL

64200116 SHOULDER RUMBLE STRIPS, 16 INCH

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
592	Sta 300+97 - 306+89 LT
5,964	Sta 308+66 - 368+30 LT
75	Sta 300+97 - 301+72 RT
<u>5,743</u>	Sta 309+32 - 366+75 RT
12,374	TOTAL

64300260 IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
1	Sta 313+96 - 314+28
<u>1</u>	Sta 360+17 - 360+49
2	TOTAL

66700305 PERMANENT SURVEY MARKER, TYPE II

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
<u>1</u>	As Directed by the Resident and Chief of Surveys (Roughly Sta. 320+50 RT)
1	TOTAL

70103815 TRAFFIC CONTROL SURVEILLANCE

<u>CAL DA</u>	<u>LOCATION</u>
	US BUS 20
<u>30</u>	As Needed & Directed by the Resident
30	TOTAL

70106800 CHANGEABLE MESSAGE SIGN

<u>CAL MO</u>	<u>LOCATION</u>
	US BUS 20
<u>2</u>	As Needed & Directed by the Resident
2	TOTAL