

SCHEDULE OF QUANTITIES

70300100 SHORT TERM PAVEMENT MARKING

<u>FOOT</u>	<u>LOCATION</u>	* (3 Applications - Prime, Binder, & Surface)
	US BUS 20	Yellow
688	Sta 299+99 - 304+26	Double Yellow - Median @ 4 Stripes
224	Sta 304+26 - 307+03	Double Yellow - Median @ 2 Stripes
132	Sta 308+49 - 310+12	Double Yellow - Median @ 2 Stripes
618	Sta 310+12 - 313+97	Double Yellow - Median @ 4 Stripes
732	Sta 360+49 - 365+05	Double Yellow - Median @ 4 Stripes
64	Sta 365+05 - 365+84	Double Yellow - Median @ 2 Stripes
100	Sta 365+84 - 368+30	Double Yellow - Centerline @ 1 Stripe
<u>336</u>	As Needed & Directed by the Resident (Contigency)	
2,892	<i>Yellow Total</i>	

	US BUS 20	White
1,096	Sta 299+99 - 368+30	Diagonal Shoulder Stripe LT - Outside
1,072	Sta 299+99 - 366+75	Diagonal Shoulder Stripe RT - Outside
752	Sta 313+96 - 360+49	Diagonal Shoulder Stripe LT - Inside
752	Sta 313+96 - 360+49	Diagonal Shoulder Stripe RT - Inside
216	Sta 304+37 - 307+03	LT Turn Lane @ 2 Stripes
216	Sta 304+37 - 307+03	RT Turn Lane @ 2 Stripes
216	Sta 308+50 - 311+13	LT Turn Lane @ 2 Stripes
<u>5,000</u>	As Needed & Directed by the Resident (Arrows, Crosswalks, Stop Bars)	
9,320	<i>White Total</i>	
<u>12,212</u>	TOTAL	

70300210 TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS

<u>SQ FT</u>	<u>LOCATION</u>	* (See Staging Plans)
	US BUS 20	White
15.6	Sta 306+09	LT Turn Arrow
15.6	Sta 306+86	LT Turn Arrow
15.6	Sta 306+09	RT Turn Arrow
15.6	Sta 306+86	RT Turn Arrow
15.6	Sta 308+60	LT Turn Arrow
<u>15.6</u>	Sta 309+40	LT Turn Arrow
93.6	TOTAL	

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

<u>FOOT</u>	<u>LOCATION</u>	* (See Staging Plans)
	US BUS 20	White
6,831	Sta 299+99 - 368+30	LT - EOP
6,831	Sta 299+99 - 368+30	RT - EOP
101	Sta 305+99 - 307+00	LT Turn Lane
173	Sta 305+27 - 307+00	RT Turn Lane
100	Sta 308+50 - 309+50	LT Turn Lane
44	Sta 304+29 - 305+99	Turkey Tracks
100	Sta 304+29 - 305+27	Turkey Tracks
<u>52</u>	Sta 309+50 - 311+50	Turkey Tracks
14,232	<i>White Total</i>	

	US BUS 20	Yellow
1,200	Sta 299+99 - 305+99	Double Yellow - Median
202	Sta 305+99 - 307+00	Double Yellow - Centerline
400	Sta 308+50 - 310+50	Double Yellow - Centerline
400	Sta 310+50 - 312+50	Double Yellow - Median
<u>11,160</u>	Sta 312+50 - 368+30	Double Yellow - Centerline
13,362	<i>Yellow Total</i>	
<u>27,594</u>	TOTAL	

70300260 TEMPORARY PAVEMENT MARKING - LINE 12"

<u>FOOT</u>	<u>LOCATION</u>	* (See Staging Plans)
	US BUS 20	Yellow
<u>55</u>	Sta 310+50 - 312+50	Median Diagonals
55	TOTAL	

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

<u>FOOT</u>	<u>LOCATION</u>	* (See Staging Plans)
	US BUS 20	White
24	Sta 307+00	Stop Bar
12	Sta 307+00	Stop Bar
<u>24</u>	Sta 308+50	Stop Bar
60	TOTAL	