

# SCHEDULE OF QUANTITIES

78009006 MODIFIED URETHANE PAVEMENT MARKING - LINE 6"

FOOT	LOCATION
	US BUS 20
216	Sta 307+24 - 308+ 32 Crosswalk - Bonus
120	Sta 308+37 Crosswalk - US Bus 20
900	Sta 324+63 - 360+ 49 Centerline - Skip Dash
1,236	TOTAL

78009008 MODIFIED URETHANE PAVEMENT MARKING - LINE 8"

FOOT	LOCATION
	US BUS 20
263	Sta 304+38 - 307+ 01 LT Turn Lane
263	Sta 304+38 - 307+ 01 RT Turn Lane
263	Sta 308+50 - 311+ 13 LT Turn Lane
14	Bonus Ave - N LT Turn Lane
123	Bonus Ave - N Painted Island
926	TOTAL

78009012 MODIFIED URETHANE PAVEMENT MARKING - LINE 12"

FOOT	LOCATION
	US BUS 20
253	Sta 299+99 - 307+ 03 Median Diagonals
347	Sta 308+48 - 314+ 12 Median Diagonals
388	Sta 314+12 - 324+ 63 Lane Diagonals
377	Sta 360+49 - 365+ 84 Median Diagonals
1,365	<i>Yellow Total</i>
	US BUS 20
156	Bonus Ave - N White Painted Island Diagonals
156	<i>White Total</i>
1,521	TOTAL

78009024 MODIFIED URETHANE PAVEMENT MARKING - LINE 24"

FOOT	LOCATION
	US BUS 20
36	Sta 307+03 White Stop Bar
35	Sta 308+49 White Stop Bar
23	Bonus Ave - N Stop Bar
18	Bonus Ave - N Stop Bar
112	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
	<i>Two-Way Amber</i>
	US BUS 20
43	Sta 300+97 - 307+ 03 Median
69	Sta 308+48 - 324+ 63 Median
30	Sta 360+49 - 366+ 75 Median
142	<i>Sub-Total</i>

*One-Way Crystal*

	US BUS 20
14	Sta 304+39 - 307+ 03 LT Turn Lane
14	Sta 304+39 - 307+ 03 RT Turn Lane
14	Sta 308+48 - 311+ 14 RT Turn Lane
46	Sta 324+63 - 360+ 49 Centerline - 1 @ 80' o.c.
88	<i>Sub-Total</i>
230	TOTAL

78200530 BARRIER WALL MARKERS, TYPE C

EACH	LOCATION
	US BUS 20
6	Sta 314+28 - 318+ 62 LT & RT
66	Sta 318+62 - 345+ 08 LT & RT
6	Sta 345+08 - 352+ 08 LT & RT
6	Sta 352+08 - 360+ 50 LT & RT
84	TOTAL