

SCHEDULE OF QUANTITIES

Z0038122 PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/4"

<u>SQ YD</u>	<u>LOCATION</u>
	US BUS 20
433.6	Sta 306+14 - 306+89 75' Milling Taper
1,078.0	Sta 306+89 - 309+25 Full 2 1/4"
333.1	Sta 309+25 - 310+00 75' Milling Taper
1,844.7	TOTAL

Z0040530 PIPE UNDERDRAIN REMOVAL

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
5,791	Sta 308+84 - 366+75 RT
5,964	Sta 308+66 - 368+30 LT (Only if Needed)
750	As Needed & Directed by the Resident
12,505	TOTAL

Z0065702 SLOPE WALL, SPECIAL

<u>SQ YD</u>	<u>LOCATION</u>
	US BUS 20
89.3	Sta 334+81 - 335+48 LT
61.8	Sta 335+90 - 336+73 RT
151.1	TOTAL

FILE NAME =	USER NAME = rundbladerr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\rundbladerr\d0275077	D206211-sh1-S00.dgn	DRAWN -	REVISED -		517	IR	BOONE	126	31				
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 64C97				
	PLOT DATE = Fri Mar 15 13:38:22 2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								