

# EARTHWORK SCHEDULE

20200100      20400800      21101605

LOCATION	EARTH EXC ( CUT )	EARTH EXC ADJ SHRINK 25%	EMBANK ( FILL )	EARTH WORK BALANCE WASTE ( + ) SHORTAGE ( - )	EARTH EXCAVATION	FURNISHED EXCAVATION	TOPSOIL FURNISH AND PLACE, 4"
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	SQ YD
US Bus 20							
308+50 - 322+00	1,906	1,430	3,077	-1,648	1,906	-1648	5,092
322+00 - 337+00	4,743	3,557	2,270	1,287	4,743	1287	6,772
337+00 - 352+00	4,876	3,657	7,626	-3,969	4,876	-3969	10,054
352+00 - 366+50	1,433	1,075	6,878	-5,803	1,433	-5803	7,240
Lawrenceville Road							
1002+25 - 1003+25	13	10	99	-89	13	-89	146
TOTAL		9,728	19,950	-10,222	12,971	10,222	29,304