

STAGING								
LOCATION		TEMPORARY CONCRETE BARRIER	REL TEMP CONCRETE BARRIER	IMPACT ATT TEMP (FULLY RED) TEST LEVEL 3	IMPACT ATT REL (FULLY RED) TEST LEVEL 3	PAVEMENT REMOVAL	PIPE CULV CL D, TY 1 48" (TEMP)	TEMPORARY PAVEMENT 8"
		FOOT	FOOT	EACH	EACH	SQ YD	FOOT	SQ YD
I-80								
STAGE 1								
1572+40 - 1576+52.5	WB	412.5		1				
1571+77.5 - 1575+90	EB	412.5		1				
STAGE 2								
1572+22.5 - 1576+37	WB		412.5		1			
1571+55 - 1575+92.5	EB		412.5		1			
MINOOKA ROAD								
STAGE 1								
56+00 - 72+50							54	2033
STAGE 2								
57+00 - 61+00		400		2				
65+86.5 - 67+36.5		150		2				
STAGE 3								
58+50 - 59+75			125		1			
65+86.5 - 67+36.5			150		2			
56+00 - 72+50						2033		
RELOCATE TCB TO PERMANENT LOCATION								
TOTAL		1375.0	1975.0	6	5	2033	54	2033

TEMPORARY PAVEMENT MARKING					
LOCATION STA. TO STA.	TEMPORARY				SHORT TERM PVT MK FOOT
	4"	6"	24"		
	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	
I-80					
STAGE 2					
1568+22.5 - 1579+10	WB				
EDGELINES	2225				
CENTERLINE		1112.5			
1568+80 - 1579+92.5	EB				
EDGELINES	2225				
CENTERLINE		1112.5			
MINOOKA ROAD					
STAGE 2					
55+82 - 72+50					
EDGELINES	3352				
CENTERLINE		3356			
STOPBAR AT SHADY OAKS				14	
STAGE 3					
59+50 - 72+16					
EDGELINES	2515				
CENTERLINE		2516			
ALONG SHADY OAKS					
EDGELINES	1194				
CENTERLINE		1194			
STOPBAR				16	
BEFORE PERMANENT MARKING					
I-80					
WESTBOUND					111
EASTBOUND					111
MINOOKA & SHADY OAKS ROADS					
EDGELINES	8361				
STOPBAR				26	
CENTERLINE		3423	960		847
TOTALS	32586	960	56		1069

PAVEMENT MARKING								
STA. TO STA.	EPOXY				MODIFIED URETHANE			RAISED REFL PAVT MARK EACH
	4"	6"	24"		4"	6"		
	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	
I-80								
WESTBOUND								
CENTERLINE							280	
EDGELINE					1112.5	1112.5		
EASTBOUND								
CENTERLINE							280	
EDGELINE					1112.5	1112.5		
MINOOKA RD								
36+57 - 41+00								
CENTERLINE			110				6	
EDGELINE		886						
41+00 - 49+90								
CENTERLINE			220				11	
EDGELINE		1780						
EB NO PASSING ZONE								
EDGELINE	890							
49+90 - 50+45								
EDGELINE		110						
DOUBLE NO PASSING ZONE								
EDGELINE	110						1	
50+45 - 64+00								
CENTERLINE			340				17	
EDGELINE		2563						
WB NO PASSING ZONE								
EDGELINE	1355							
64+00 - 73+32								
CENTERLINE			230				12	
EDGELINE		1864						
SHADY OAKS RD								
CL NO PASSING ZONE								
EDGELINE	1068						7	
STOP BARS		1158		26				
TOTAL	3423	8361	900	26	2225	2225	560	