

I:\Projects\228-1001-107 Bridges - FTB 153-37\Drawings\1500 Sheets\0366542-ht-500_3.dgn
 I:\Projects\228-1001-107 Bridges - FTB 153-37\Drawings\1500 Sheets\0366542-ht-500_3.dgn

90% FED.
10% STATE

CONSTRUCTION CODES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES		
				ROADWAY 0004 RURAL	SN 038-0013 0014 RURAL	SN 038-0014 0014 RURAL
50300100	FLOOR DRAINS	EACH	20		10	10
50300225	CONCRETE STRUCTURES	CU YD	566.8		283.4	283.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1223		611.5	611.5
50300260	BRIDGE DECK GROOVING	SQ YD	3696		1848	1848
50300280	CONCRETE ENCASEMENT	CU YD	6.8		3.4	3.4
50300300	PROTECTIVE COAT	SQ YD	4472		2236	2236
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.5	0.5
50500505	STUD SHEAR CONNECTORS	EACH	21420		10710	10710
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	425,420		212,710	212,710
50800515	BAR SPLICERS	EACH	3110		1555	1555
51100100	SLOPE WALL, 4 IN	SQ YD	1691		845.5	845.5
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	1426		713	713
51202305	DRIVING PILES	FOOT	1426		713	713
51203200	TEST PILE STEEL HP 12X53	EACH	5		3	2

* SPECIALTY ITEM

Rev.



USER NAME: WWH	DESIGNED: -	REVISED: -
PLOT SCALE: 600.0000 "/> <td>DRAWN: -</td> <td>REVISED: -</td>	DRAWN: -	REVISED: -
PLOT DATE: 8/21/2012	CHECKED: -	REVISED: -
	DATE: -	REVISED: -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-57 OVER OLD ROUTE 45 AND ILLINOIS CENTRAL RAILROAD

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(38-2)HBYR, HVBR-1	ILLINOIS	146	5
CONTRACT NO. 66942				
ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 3 OF 7 SHEETS STA. TO STA.