	CODE NO.	ITEM	UNIT	TOTAL QUANTITY (90% FED. 10% STATE)	CONSTRUCTION CODES: ROADWAY 0004 RURAL	SN 038-0013 0014 RURAL	SN 038-0014 0014 RURAL
	51500100	NAME PLATES	EACH	2		1	1
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	232		116	116
	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	56		28	28
	52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	14		7	7
	52100500	ANCHOR BOLTS, 1"	EACH	84		42	42
	52100505	ANCHOR BOLTS, 5/8"	EACH	56		28	28
	52100510	ANCHOR BOLTS, 3/4"	EACH	28		14	14
	58700300	CONCRETE SEALER	SQ FT	4557		2278.5	2278.5
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	171		85.5	85.5
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	15.3	15.3		
	60617310	PAVED DITCH, TYPE B-22	FOOT	393	393		
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1537.5	1537.5		
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6		
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
*	63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2		

* SPECIALTY ITEM

Rev.

TERRA ENGINEERING LTD.

USER NAME = WAN	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 600.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 8/21/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-57 OVER OLD ROUTE 45 AND ILLINOIS CENTRAL RAILROAD

SCALE: | SHEET NO. 4 OF 7 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(38-2)HBVR, HVBR-1	IROQUOIS	146	6

CONTRACT NO. 66942

ILLINOIS FED. AID PROJECT