90% FED.
10% STATE

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES		
					ROADWAY 0004 RURAL	SN 038-0013 0014 RURAL	SN 038-0014 0014 RURAL
*	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	13072	13072		
*	78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	909	909		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	22	22		
*	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	7	7		
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	22	22		
*	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2 " DIA. PVC	FOOT	748		374	374
	X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	1600	1600		
	X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	9	9		
	X2020502	BRACED EXCAVATION	CU YD	131		65.5	65.5
	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	351		175.5	175.5
	X0324589	PIPE UNDERDRAIN OUTLET EXTENSION FOR 4" PIPE	EACH	2	2		
	X6650208	WOVEN WIRE FENCE REMOVAL AND REPLACEMENT	FOOT	285	285		
	X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2	2		

* 14 SPECIALTY ITEM

Rev.

TERRA ENGINEERING LTD.

USER NAME = WAH	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 600.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 8/24/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-57 OVER OLD ROUTE 45 AND ILLINOIS CENTRAL RAILROAD

SCALE: | SHEET NO. 6 OF 7 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(38-21)HBVR, HVBR-1	IROQUOIS	146	8

CONTRACT NO. 66942

ILLINOIS FED. AID PROJECT