

INLET AND PIPE PROTECTION	
LOCATION	EA
EAST MEDIAN	1
WEST MEDIAN	1
<b>TOTAL</b>	<b>2</b>

CLASS SI CONCRETE (OUTLET)	
LOCATION	CU YD
STA 1035+00 LT	3.8
STA 1035+00 RT	3.8
STA 1040+00 LT	3.8
STA 1040+00 RT	3.8
<b>TOTAL</b>	<b>15.3</b>

PAVED DITCH, TYPE B-22			
STATION	TO	STATION	FOOT
1033+11	TO	1035+15	203.3
1040+08	TO	1041+98	189.7
<b>TOTAL</b>			<b>393.0</b>

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS				
STATION	TO	STATION	OFFSET	FOOT
1032+98	TO	1035+94	56' LT	262.5
1039+70	TO	1040+89	14' LT	75.0
1040+06	TO	1043+53	56' LT	312.5
1033+00	TO	1034+97	56' RT	162.5
1034+34	TO	1035+53	14' RT	75.0
1039+29	TO	1043+50	56' RT	387.5
298+44	TO	302+08	19' LT	262.5
<b>TOTAL</b>				<b>1537.5</b>

TRAFFIC BARRIER TERMINAL, TYPE 6			
DIRECTION	STATION	OFFSET	EACH
NB	1035+94	56' LT	1
NB	1039+70	14' LT	1
NB	1040+06	56' LT	1
SB	1034+97	14' RT	1
SB	1035+53	56' RT	1
SB	1039+29	56' RT	1
<b>TOTAL</b>			<b>6</b>

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT			
DIRECTION	STATION	OFFSET	EACH
NB	1041+27	14' LT	1
SB	1033+96	14' RT	1
<b>TOTAL</b>			<b>2</b>

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED			
DIRECTION	STATION	OFFSET	EACH
OR45	298+44	19' LT	1
OR45	302+03	19' LT	1
<b>TOTAL</b>			<b>2</b>

GUARDRAIL REMOVAL					
DIRECTION	STATION	TO	STATION	FOOT	
NB	1033+00	TO	1036+08	56' LT	308.44
NB	1040+00	TO	1043+62	14' LT	361.27
NB	1040+02	TO	1043+50	56' LT	348.42
SB	1032+12	TO	1035+52	56' RT	339.79
SB	1039+14	TO	1043+50	14' RT	436.40
SB	1033+00	TO	1035+22	56' RT	221.60
OR45	298+44	TO	302+08	24' LT	349.28
<b>TOTAL</b>				<b>2365.2</b>	

SHOULDER RUMBLE STRIPS, 16 INCH				
DIRECTION	STATION	TO	STATION	FOOT
NB	1033+00	TO	1035+74	547.2
NB	1040+06	TO	1043+50	688.0
SB	1033+00	TO	1035+17	433.4
SB	1039+49	TO	1043+50	801.7
<b>TOTAL</b>				<b>2470.2</b>

SHORT TERM PAVEMENT MARKING					
DIRECTION	STATION	TO	STATION	# APPLICATIONS	FOOT
NB CL	1033+00	TO	1062+90	2	543.6
NB SHLD	1033+00	TO	1062+90	2	11960.0
SB CL	1010+00	TO	1043+50	2	609.1
SB SHLD	1010+00	TO	1043+50	2	13400.0
<b>TOTAL</b>					<b>26512.7</b>

TEMPORARY PAVEMENT MARKING - LINE 4"		
STAGE	LOCATION	FOOT
1	NORTHBOUND- OUTSIDE LANE	3138.8
1	NORTHBOUND- INSIDE LANE	1639.6
1	SOUTHBOUND- OUTSIDE LANE	4203.7
1	SOUTHBOUND- INSIDE LANE	1606.1
2	NORTHBOUND- OUTSIDE LANE	3266.2
2	NORTHBOUND- INSIDE LANE	3270.0
2	SOUTHBOUND- OUTSIDE LANE	2704.1
2	SOUTHBOUND- INSIDE LANE	3300.4
<b>TOTAL</b>		<b>23128.9</b>

WORK ZONE PAVEMENT MARKING REMOVAL					
STAGE	DIRECTION	STATION	TO	STATION	SQ FT
1	NB- EXIST	1031+39	TO	1047+81	547.6
1	NB- TEMP	1010+00	TO	1044+83	1592.8
1	SB- EXIST	1028+73	TO	1044+83	536.7
1	SB- TEMP	1031+39	TO	1062+90	1936.6
2	NB	1030+09	TO	1062+90	2178.7
2	SB	1013+64	TO	1046+77	2001.5
3	NB CL	1033+00	TO	1062+90	90.6
3	NB SHLD	1033+00	TO	1062+90	1993.3
3	SB CL	1010+00	TO	1043+50	101.5
3	SB SHLD	1010+00	TO	1043+50	2233.3
<b>TOTAL</b>					<b>13212.7</b>

TEMPORARY CONCRETE BARRIER		
STAGE	LOCATION	FOOT
1	NORTHBOUND	1262.5
1	SOUTHBOUND	1287.5
2	NORTHBOUND	12.5
<b>TOTAL</b>		<b>2562.5</b>

RELOCATE TEMPORARY CONCRETE BARRIER		
STAGE	LOCATION	FOOT
2	NORTHBOUND	1262.5
2	SOUTHBOUND	1287.5
<b>TOTAL</b>		<b>2550.0</b>

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"				
DIRECTION	STATION	TO	STATION	FOOT
NB	1030+00	TO	1062+90	822.5
SB	1010+00	TO	1047+00	925.0
<b>TOTAL</b>				<b>1747.5</b>

EPOXY PAVEMENT MARKING - LINE 4"				
DIRECTION	STATION	TO	STATION	FOOT
NB	1030+00	TO	1062+90	6580.0
SB	1010+00	TO	1047+00	6491.2
<b>TOTAL</b>				<b>13071.2</b>

EPOXY PAVEMENT MARKING - LINE 8"				
DIRECTION	STATION	TO	STATION	FOOT
SB	1010+00	TO	1019+09	908.8
<b>TOTAL</b>				<b>908.8</b>

RAISED REFLECTIVE PAVEMENT MARKER				
DIRECTION	STATION	TO	STATION	EACH
NB	1033+00	TO	1035+74	5
NB	1040+06	TO	1043+50	6
SB	1033+00	TO	1035+17	4
SB	1039+49	TO	1043+50	7
<b>TOTAL</b>				<b>22</b>



USER NAME = WAH	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 8/21/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES		
I-57 OVER OLD ROUTE 45 AND ILLINOIS CENTRAL RAILROAD		
SCALE:	SHEET NO. 3 OF 4 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(38-2)HBVR, HVBR-1	IROQUOIS	146	15
CONTRACT NO. 66942				
ILLINOIS FED. AID PROJECT				