

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE ROADWAY	100% STATE ROADWAY
				0005 RURAL	0005 URBAN
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	1365	1146	219
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	156	156	
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	169	142	27
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	660	506	154
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	23		23
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	142		142
44201299	DOWEL BARS 1 1/2"	EACH	1848	1400	448
44213000	PATCH REINFORCEMENT	SQ YD	1690	1444	246
44213100	PAVEMENT FABRIC	SQ YD	825	506	319
44213200	SAW CUTS	FOOT	14832	12060	2772
44213204	TIE BARS 3/4"	EACH	151	61	90
67100100	MOBILIZATION	L SUM	1	0.50	0.50
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	40	35	5
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.50	0.50
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	33	28	5
* 78009004	MODIFIED URETHANE PAVEMENT MARKING LINE 4"	FOOT	2101	1566	535
* 78009006	MODIFIED URETHANE PAVEMENT MARKING LINE 6"	FOOT	1510	1340	170
* 78009008	MODIFIED URETHANE PAVEMENT MARKING LINE 8"	FOOT	129	93	36
X0326458	PAVEMENT REPLACEMENT, SPECIAL	SQ YD	250	125	125
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOURL	272	136	136
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	1.14	0.57	0.57
X4404400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	250	125	125
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	L SUM	1	0.50	0.50

13 • SPECIALITY ITEM

FILE NAME *	USER NAME * patelju	DESIGNED - YOGESH PATEL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\patelju\dr332581\0366036-sht-detaila.dgn	DRAWN - YOGESH PATEL	REVISED -	39			*	LASALLE	17	3	
PLOT SCALE * 1/8"=1'-0"	CHECKED - RON WOODSHANK	REVISED -	*03 PAVEMENT PATCHING 2014-2			CONTRACT NO. 66C86				
PLOT DATE * 5/7/2013	DATE -	REVISED -	SCALE:			SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	[ILLINOIS]		