

SCHEDULES
NORTHBOUND RAMP PATCHING

LOCATION	RAMP LENGTH	RAMP WIDTH	CLASS A PATCHES			CLASS B PATCHES			PAV'T REINF	PAV'T FABRIC	DOWEL BARS	SAW CUTS	TIE BARS	
			TYPE II 10"	TYPE III 10"	TYPE IV 10"	TYPE II 10"	TYPE III 10"	TYPE IV 10"						
EXIT NO.	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SO YD	FOOT	EACH		
41	EXIT	6	16	11					11			76		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
	ENTRANCE	6	20	13					13			92		
48	ENTRANCE	6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	20	13					13			92		
		6	20	13					13			92		
51	EXIT	6	24		16				16			108		
	ENTRANCE	6	16					11		11	28	60		
		6	16					11		11	28	60		
52	EXIT	6	16					11		11	28	60		
54	EXIT	6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
	ENTRANCE	6	16	11					11			76		
		6	16	11					11			76		
		6	16	11					11			76		
57	EXIT	6	16	11								76		
		6	16	11								76		
		80	16					142		142	28	208	80	
		6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
66	EXIT	6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
	ENTRANCE	6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16					11		11	28	60		
72	ENTRANCE	13	16						23		23	28	74	
		6	16					11		11	28	60		
		6	16					11		11	28	60		
		6	16	11					11	11	28	60		
TOTALS			138	16			319	23	142	154	484	868	3014	80

- CLASS A PATCHES FOR RAMPS = WHERE RAMP PAVEMENT ABUTS EXISTING MAINLINE PAVEMENT
- CLASS B PATCHES FOR RAMPS = WHERE RAMP PAVEMENT DOES NOT ABUT EXISTING MAINLINE PAVEMENT