

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				STATE 100%	
				ROADWAY 0005	
				RURAL	URBAN
20200100	EARTH EXCAVATION	CU YD	151	91	60
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	331	200	131
31101810	SUBBASE GRANULAR MATERIAL, TYPE B 12"	SO YD	331	200	131
44200645	CLASS A PATCHES, TYPE II, 16 INCH	SO YD	177	99	78
44200647	CLASS A PATCHES, TYPE IV, 16 INCH	SO YD	154	101	53
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SO YD	27	27	
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	12	12	
44201299	DOWEL BARS 1 1/2"	EACH	10	10	
44213000	PATCHING REINFORCEMENT	SO YD	331	200	131
44213100	PAVEMENT FABRIC	SO YD	385	254	131
44213200	SAW CUTS	FOOT	1757	1079	678
44213204	TIE BARS 3/4"	EACH	47	27	20
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6	4	2
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	15	15
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	247	149	98
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	300	190	110
X0325969	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE BOARD	CAL DA	30	15	15
X0326867	RADAR SPEED TRAILER	CAL MO	1	0.5	0.5
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	60	30	30
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	L SUM	1	0.5	0.5

* SPECIALITY ITEMS

FILE NAME : c:\pr-work\pwidest\woodshankr1\d0337540\66C95-ahd-details.dgn	USER NAME : woodshankr1	DESIGNED - RW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLT SCALE : 100:0000 / 1in.	CHECKED -	REVISED -	80			D3 PATCHING 2014-6	GRUNDY	13	3	
PLT DATE : 5/6/2013	DATE -	REVISED -	CONTRACT NO. 66C95			ILLINOIS FED. AID PROJECT				
SCALE:		SHEET NO. 1 OF 1 SHEETS				STA.	TO STA.			