

SCHEDULES
CLASS A PATCHES
NORTHBOUND LANES

LOCATION MILE POST	PASS LANE FEET	DRIVE LANE FEET	PASSING LANE				DRIVING LANE			
			TYPE II 13" SQ YD	PATCH REINF. SQ YD	PAV'T FABRIC SQ YD	SAW CUTS FOOT	TYPE II 13" SQ YD	PATCH REINF. SQ YD	PAV'T FABRIC SQ YD	SAW CUTS FOOT
218.40		10					13	13	13	56
218.55		6					8	8	8	48
218.70		6					8	8	8	48
219.70		6					8	8	8	48
219.73		6					8	8	8	48
219.75		6					8	8	8	48
219.90		6					8	8	8	48
220.10		6					8	8	8	48
220.45		6					8	8	8	48
220.50		6					8	8	8	48
220.54	6		8	8	8	48				
220.60		6					8	8	8	48
220.82		6					8	8	8	48
221.20		6					8	8	8	48
224.40	6		8	8	8	48				
224.50	6	6	8	8	8	48	8	8	8	48
224.65		6					8	8	8	48
226.30		6					8	8	8	48
226.98	6	6	8	8	8	48	8	8	8	48
227.20	6	6	8	8	8	48	8	8	8	48
227.75	6	6	8	8	8	48	8	8	8	48
228.25		6					8	8	8	48
229.01	6	6	8	8	8	48	8	8	8	48
229.10	6	6	8	8	8	48	8	8	8	48
229.98	6	6	8	8	8	48	8	8	8	48
230.40		6					8	8	8	48
230.98		6					8	8	8	48
231.15		6					8	8	8	48
231.56	6	6	8	8	8	48	8	8	8	48
231.60		6					8	8	8	48
231.61		6					8	8	8	48
232.05	10	6	13	13	13	56	8	8	8	48
231.10		6					8	8	8	48
231.20		6					8	8	8	48
232.30		6					8	8	8	48
232.32		6					8	8	8	48
232.35		6					8	8	8	48
232.45		6					8	8	8	48
232.50		6					8	8	8	48
232.54		6					8	8	8	48
232.55		10					13	13	13	56
232.57		6					8	8	8	48
232.58		6					8	8	8	48
232.59		10					13	13	13	56
232.60		6					8	8	8	48
232.61		6					8	8	8	48
232.68		6					8	8	8	48
232.70		6					8	8	8	48
232.72		6					8	8	8	48
232.73		6					8	8	8	48
232.78		6					8	8	8	48
232.85		6					8	8	8	48
NB TOTALS	70	312	93	93	93	536	415	415	415	2424

FILE NAME =	USER NAME = poteluj	DESIGNED - RW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\p\p\poteluj\08337548\0366	95-shi-detail.dgn	DRAWN - RW	REVISED -			55	D3 PATCHING 2014-B	GRUNDY	13	5	
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -			SCALE:		SHEET NO. 1 OF 1 SHEETS		STA. TO STA.	
	PLOT DATE = 4/3/2013	DATE -	REVISED -			ILLINOIS REG. AID PROJECT CONTRACT NO. 66D02					