100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES		
				ROADWAY 0004 RURAL	SN 090-0179 0011 RURAL	MOWING 0004 RURAL
28000500	INLET AND PIPE PROTECTION	EACH	2	2	0	0
28100107	STONE RIPRAP, CLASS A4	SQ YD	287	0	287	0
28100109	STONE RIPRAP, CLASS A5	SQ YD	3732	0	3732	0
28200200	FILTER FABRIC	SQ YD	4019	0	4019	0
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1850	1850	0	0
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	147	147	0	0
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	44	44	0	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	267	267	0	0
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	88	88	0	0
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	58	58	0	0
44000100	PAVEMENT REMOVAL	SQ YD	266	266	0	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	15	15	0	0
44004250	PAVED SHOULDER REMOVAL	SQ YD	2412	2412	0	0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	152	152	0	0

* SPECIALTY ITEM