100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES		
				ROADWAY 0004 RURAL	SN 090-0179 0011 RURAL	MOWING 0004 RURAL
50500505	STUD SHEAR CONNECTORS	EACH	3564	0	3564	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	120810	160	120650	0
50800515	BAR SPLICERS	EACH	94	0	94	0
51202100	FURNISHING STEEL PILES HP14X117	FOOT	1774	0	1774	0
51202305	DRIVING PILES	FOOT	1774	0	1774	0
51204100	TEST PILE STEEL HP14X117	EACH	3	0	3	0
51500100	NAME PLATES	EACH	1	0	1	0
52100520	ANCHOR BOLTS, 1"	EACH	36	0	36	0
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	364	364	0	0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	118	0	118	0
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1	0	0
60500060	REMOVING INLETS	EACH	1	1	0	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	45	45	0	0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	662.5	662.5	0	0

* SPECIALTY ITEM

TERRA ENGINEERING LTD.

USER NAME = WAH	DESIGNED - CL	REVISED -	
	DRAWN - WAH	REVISED -	
PLOT SCALE = 2.0000 ' / in.	CHECKED - KJC/HTL	REVISED -	
PLOT DATE = 12/13/2012	DATE - 10/04/12	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 116 OVER TEN MILE CREEK

SCALE: NTS | SHEET NO. 4 OF 7 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	(102B-1)BR	TAZEWELL	89	7

CONTRACT NO. 68671

ILLINOIS FED. AID PROJECT