



FRAMING PLAN



GIRDER ELEVATION

- Notes:
1. All flange and web splice plates, except filler plates, shall be M270 Grade 50W and meet notch toughness requirements.
 2. Load carrying components designated "NTR" shall conform to the Supplemental Requirements for Notch Toughness, Zone 2.
 3. All girder flanges, webs and bearing stiffeners shall be M270 Grade 50W.
 4. All diaphragms shall be installed as steel is erected and secured with erection pins and bolts except as otherwise noted.
 5. For Section A-A, Detail B see sheet S14 of S22.

M:\JL RT 116 OVER TEN MILE CREEK\CIVIL\Structural\Final Plans\SHEETS\0468671-013-Framing Plan.dgn



USER NAME = cvm	DESIGNED - OY	REVISED -
FILE NAME = D468671-013-Framing Plan.dgn	CHECKED - DB	REVISED -
PLOT DATE = 10/4/2012	DRAWN - CM	REVISED -
	CHECKED - JB	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FRAMING PLAN
STRUCTURE NO. 090-0179

SHEET NO. S13 OF S22 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	(102B-1) BR	TAZEWELL	89	56
CONTRACT NO. 68671			ILLINOIS FED. AID PROJECT	