

PAINT PAVEMENT MARKING, 4"						
CENTERLINE (YELLOW)				NO PARKING AREA (YELLOW)		
STATION	LENGTH	SKIP DASH	SOLID	STATION	LOCATION**	FOOT
	FOOT	FOOT	FOOT			
STA. 482+98 TO STA. 520+73*	3775	943.8		LT. STA. 557+70	1	94
STA. 520+73 TO STA. 530+00	927	231.8	927.0	TO LT. STA.	2	60.4
STA. 530+00 TO STA. 547+13	1713		3426.0	561+50	3	60.2
STA. 547+13 TO STA. 552+41*	528	132.0	528.0	RT. STA. 557+70	4	96
STA. 552+41 TO STA. 568+70	1629	407.3		TO RT. STA.	5	122.3
STA. 568+70 TO STA. 667+98	9928	2482.0		RT. STA. 561+50	6	122.3
<b>TOTAL</b>		<b>9,078</b>		TO RT. STA.	7	122.3
				LT. STA. 561+50	8	122.3
				TO LT. STA.	9	122.3
EDGELINE (WHITE)					10	122.3
STATION	LENGTH	SOLID		LT. STA. 565+00	11	94
	FOOT	FOOT		TO LT. STA.	12	69.5
LT/RT STA. 482+98 TO STA. 55	7472	14944		568+70	13	110.9
RT STA. 557+70 TO STA. 561+5	380	380			14	104.6
LT/RT STA. 561+50 TO STA. 56	350	700		RT. STA. 565+00	15	150.5
LT STA. 576+00 TO STA. 579+8	380	380		TO RT. STA.	16	88.5
LT/RT STA. 579+80 TO STA. 66	8818	17636		568+70	17	80.3
<b>TOTAL</b>		<b>34,040</b>			18	60.2
				LT. STA. 568+70	19	135.3
				TO LT. STA.	20	76.4
*NO PASSING ZONE				RT. STA. 568+70	21	108.8
NB STA. 520+73 TO STA. 547+13				TO RT. STA.	22	91.5
SB STA. 530+00 TO STA. 552+41					23	97.2
SHALL BE VERIFIED BY OPERATIONS. SEE GENERAL NOTE.				LT. STA. 572+40	24	97.2
				TO LT. STA.	25	59
				576+00	26	89.4
					27	103.7
				RT. STA. 572+40	28	104.5
				TO RT. STA.	29	93.5
				RT. STA. 576+00	30	97.3
				TO RT. STA.	31	95.1
<b>GRAND TOTAL</b>		<b>46,170</b>		<b>TOTAL</b>		<b>3,052</b>

\*\*See detail for locations

SHORT TERM PAVEMENT MARKING	
LOCATION	LENGTH (FT)
STA 482+98 TO STA 669+40	185
<b>TOTAL</b>	<b>555</b>

\*NOTE: 3 APPLICATIONS

WORK ZONE PAVT MARKING REMOVAL			
LOCATION	LENGTH (FT)	WIDTH (FT)	AREA (SQFT)
STA 482+98 TO STA 669+40	1850	0.3333	617
530+24 TO STA 586+09	56	0.3333	19
<b>TOTAL</b>			<b>635</b>

\*NOTE: 1 APPLICATION

TRAFFIC CONTROL AND PROTECTION				
LOCATION	STANDARD	STANDARD	STANDARD	STANDARD
	701306	701336	701501	701801
	LSUM	LSUM	LSUM	LSUM
ENTIRE JOBSITE	1.0	1.0	1.0	1.0
<b>TOTAL</b>	<b>1.0</b>	<b>1.0</b>	<b>1.0</b>	<b>1.0</b>

LOCATION	ENGINEER'S	MOBILIZATION	CONSTRUCTION	CONSTRUCTING
	FIELD OFFICE,			
	TYPE A		LAYOUT	TEST STRIP
	CAL MONTH	L SUM	L SUM	EACH
JOBSITE	3.0	1.0	1.0	1.0
<b>TOTAL</b>	<b>3.0</b>	<b>1.0</b>	<b>1.0</b>	<b>1.0</b>

PAINT PAVEMENT MARKING, 24"		
STOP BAR (WHITE)		
STATION	LOCATION	WIDTH (FT)
567+95	SANTA FE/IL 117 ( EB)	12.0
568+70	SANTA FE/IL 117 ( WB)	12.0
569+50	MAIN/SANTA FE (NB)	12.0
569+50	IL 117/SANTA FE (SB)	12.0
<b>TOTAL</b>		<b>48.0</b>