

# SCHEDULE OF QUANTITIES

## PAVEMENT MARKING (SHEET 2 OF 2)

### MODIFIED URETHANE PAVEMENT MARKING, LINE 8"

LOCATION	RAMP	STATION	TO	STATION	# OF WHITE STRIPES	# OF YELLOW STRIPES	LENGTH (FOOT)	MODIFIED URETHANE PAVEMENT MARKING, 8" 78009008 (FEET)	
								WHITE	YELLOW
SB URBAN RAMPS:									
I-55 INTERCHANGE- SB MAINLINE	SB	83+63.00		89+88.00	2	0	625.0	1,250.0	0.0
I-55 INTERCHANGE- SB MAINLINE	SB	116+13.00		126+10.00	1	0	997.0	997.0	0.0
I-55 INTERCHANGE- SB MAINLINE	SB	126+10.00		129+10.00	1	0	300.0	300.0	0.0
I-55 INTERCHANGE - RAMP A	GORE	0+40.00		4+83.00	1	0	443.0	443.0	0.0
TR 181 RAMP D	GORE	11+27.00		14+27.00	2	0	300.0	600.0	0.0
TR 181 RAMP A	GORE	3+04.00		6+60.00	2	0	356.0	712.0	0.0
								WHITE	YELLOW
SUB TOTAL SB URBAN								4,302.0	0.0
GRAND TOTAL								4,302.0	
ROUNDED TOTAL								4,310.0	

### MODIFIED URETHANE PAVEMENT MARKING, LINE 12"

LOCATION	STATION	WIDTH AT STATION (FOOT)	TO	STATION	WIDTH AT STATION (FOOT)	# OF WHITE STRIPES	# OF YELLOW STRIPES	LENGTH (FOOT)	AVG WIDTH (FOOT)	NUMBER OF (EACH)	MODIFIED URETHANE PAVEMENT MARKING, 12" 78009012 (FEET)	
											WHITE	YELLOW
SB URBAN RAMPS:												
I-55 INTERCHANGE - SB MAINLINE	83+63.00	0.0		89+88.00	19.5	1	0	625.0	9.8	21.0	289.6	0.0
I-55 INTERCHANGE - SB MAINLINE	116+13.00	0.0		121+68.00	12.0	1	0	555.0	6.0	19.0	161.2	0.0
I-55 INTERCHANGE - SB MAINLINE	121+68.00	30.0		123+28.00	18.5	1	0	160.0	24.3	6.0	205.8	0.0
I-55 INTERCHANGE - SB MAINLINE	123+28.00	18.5		126+10.00	0.0	1	0	282.0	9.3	10.0	130.8	0.0
											WHITE	YELLOW
SUB TOTAL SB URBAN RAMPS											787.4	0.0
GRAND TOTAL											787.4	
ROUNDED TOTAL											790.0	

### PAVEMENT MARKING SUMMARY

	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" 78003110 (FEET)	MODIFIED URETHANE PAVEMENT MARKING, LINE 4" 78009004 (FEET)	MODIFIED URETHANE PAVEMENT MARKING, LINE 8" 78009008 (FEET)	MODIFIED URETHANE PAVEMENT MARKING, LINE 12" 78009012 (FEET)
SB URBAN TOTAL	2,737.8	24,061.3	4,302.0	787.4
SB URBAN ROUNDED	2,740.0	24,070.0	4,310.0	790.0
SB RURAL TOTAL	810.8	7,355.2	0.0	0.0
SB RURAL ROUNDED	820.0	7,360.0	0.0	0.0
<b>TOTAL</b>	<b>3,560.0</b>	<b>31,430.0</b>	<b>4,310.0</b>	<b>790.0</b>