

SCHEDULE OF QUANTITIES

EARTH EXCAVATION

LOCATION	EARTH EXCAVATION 20200100 (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	FURNISHED EXCAVATION 20400800 (CU YD)
URBAN SECTION					
SOUTHBOUND:					
I-39 SB LEFT STA. 156+23.97 - 198+61.67	0.0	0.0	148.0	-148.0	148.0
I-39 SB RIGHT STA. 156+23.97 - 198+61.67	0.0	0.0	266.3	-266.3	266.3
I-39 SB RAMP LEFT	52.2	39.2	1,354.2	-1,315.0	1,315.0
I-39 SB RAMP RIGHT	8.6	6.4	889.9	-883.4	883.4
TR 181 RAMP A LEFT	242.3	181.7	309.9	-128.2	128.2
TR 181 RAMP A RIGHT	0.0	0.0	5.4	-5.4	5.4
TR 181 RAMP D LEFT	0.0	0.0	152.0	-152.0	152.0
TR 181 RAMP D RIGHT	0.0	0.0	6.7	-6.7	6.7
MEDIAN CROSSOVER STA. 149+00.00 SOUTH	0.0	0.0	2.6	-2.6	2.6
MEDIAN CROSSOVER STA. 149+00.00 NORTH	0.0	0.0	2.0	-2.0	2.0
RURAL SECTION					
SOUTHBOUND:					
I-39 SB LEFT STA. 198+61.67 - 231+65.00	0.0	0.0	516.4	-516.4	516.4
I-39 SB RIGHT STA. 198+61.67 - 231+65.00	0.0	0.0	632.2	-632.2	632.2
SB URBAN:	303.1				2,909.7
SB URBAN ROUNDED:	310.0				2,910.0
SB RURAL:	0.0				1,148.6
SB RURAL ROUNDED:	0.0				1,150.0
GRAND TOTAL:	303.1				4,058.4
ROUNDED TOTAL:	310.0				4,060.0

NOTES:

1. THE SHRINKAGE FACTOR USED IS 25%.
2. SHRINKAGE, EMBANKMENT, AND BALANCE IS FOR INFORMATION ONLY.
3. NO PAYMENT WILL BE ALLOWED FOR OVERHAUL
4. EXCAVATION REQUIRED FOR PCC BASE COURSE, FULL DEPTH BITUMINOUS PAVEMENT, BITUMINOUS SHOULDERS, BITUMINOUS BASE COURSE AND AGGREGATE SHOULDER IS MEASURED AND PAID FOR AS EARTH EXCAVATION

CHANGEABLE MESSAGE SIGN

LOCATION	CHANGEABLE MESSAGE SIGN X7015005 (CALENDAR DAYS)			
	NB URBAN	NB RURAL	SB URBAN	SB RURAL
I-39 SB START				14
I-55 SB START			14	
TR 181 RAMP D			7	
TOTAL	0	0	21	14
TOTAL	35			

FRAMES AND GRATES TO BE ADJUSTED

LOCATION	STATION	OFFSET	FRAMES AND GRATES TO BE ADJUSTED 60300105 (EACH)
SB URBAN	193+30	54'	1
		LT	1
		SB URBAN	1
		SB RURAL	0
		TOTAL	1

SURVEY MARKER – TYPE 2 (SPECIAL)

LOCATION	STATION	OFFSET	NORTHING	EASTING	SURVEY MARKER, TYPE 2 (SPECIAL) XZ193400 (EACH)	
SB URBAN	POT 2	88+30.41	0.0'	1,411,142.057	796,138.656	1
SB URBAN	PT 1	115+78.68	0.0'	1,412,814.444	797,994.337	1
SB URBAN	PC 43	145+05.83	0.0'	1,415,730.324	798,250.993	1
SB URBAN	PT 42	156+36.57	0.0'	1,416,859.773	798,294.223	1
					SB URBAN	4
					TOTAL	4