SCHEDULE OF QUANTITIES

EROSION CONTROL

PERIMETER EROSION BARRIER

PERIMETER EROSION BARRIER 28000400 (FOOT)				
LOCATION	STATION	OFFSET	FEATURE	LENGTH (FT)
SB RURAL	232+50.0	SBDS	BC END	30.0
SB RURAL	229+50.0	SBDS	PCPC END	75.0
SB RURAL	222+00.0	SBDS	REVET. MAT	500.0
SB RURAL	204+50.0	SBDS	PCPC END	80.0
RAMP A TR 181 URBAN	9+00.0	RT	DITCH	30.0
SB URBAN	186+25.0	SBDS	PCPC END	40.0
SB URBAN	178+10.0	SBDS	PAVED DITCH	10.0
SB URBAN	175+00.0	SBDS	BC END	145.0
RAMP D TR 181 URBAN	8+15.0	RT	BC END	50.0
SB URBAN	125+64.29	SBDS	BRIDGE	50.0
SB URBAN	125+64.29	MEDIAN	BRIDGE	50.0
SB URBAN	124+35.08	SBDS	BRIDGE	100.0
SB URBAN	124+35.08	MEDIAN	BRIDGE	50.0
SB URBAN	100+00.0	LT	PCPC END	80.0
SB URBAN	94+50.0	LT	PCPC END	90.0
SB URBAN	90+50.0	LT	DITCH	435.0
SB URBAN	100+00.0	RT	PCPC END	80.0
SB URBAN	94+50.0	RT	PCPC END	90.0
		SB URBAN TOTAL		1,300.0
		SB URBAN ROUNDED		1,300.0
		SB RURAL TOTAL		685.0
		SB RURAL ROUNDED		690.0
		SB TOTAL		1,985.0
		SB ROUNDED TOTAL		1,990.0

INLET AND PIPE PROTECTION

INLET AND PIPE PROTECTION 28000500 (EACH)				
LOCATION	STATION	OFFSET	FEATURE	# EACH
SB URBAN	141+11.0	47.1' LT	MEDIAN INLET	1.0
SB URBAN	148+72.0	53.5' LT	X-OVER INLET	1.0
SB URBAN	149+36.0	53.8' LT	X-OVER OUTLET	1.0
SB URBAN	153+50.0	157.4' LT	INLET	1.0
SB URBAN	153+51.0	50.7' LT	MEDIAN INLET	1.0
SB URBAN	175+00.0	0.0'	MEDIAN INLET	1.0
SB URBAN	191+00.0	0.0'	MEDIAN INLET	1.0
SB RURAL	204+50.0	0.0'	MEDIAN INLET	1.0
SB RURAL	219+70.0	0.0'	MEDIAN INLET	1.0
SB RURAL	229+50.0	0.0'	MEDIAN INLET	1.0
			SB URBAN	7.0
			SB RURAL	3.0
			TOTAL	10.0

TEMPORARY DITCH CHECKS

TEMPORARY DITCH CHECKS 28000305 (FOOT)				
LOCATION		STATION	SB URBAN	SB RURAL
SB URBAN	LEFT DITCH	194+00.00	10.0	0.0
RURAL	MEDIAN DITCH	212+00.00	0.0	10.0
RURAL	MEDIAN DITCH	217+00.00	0.0	10.0
RURAL	MEDIAN DITCH	226+00.00	0.0	10.0
		TOTAL	10.0	30.0
		TOTAL	40.0	