

# SCHEDULE OF QUANTITIES

## PIPE UNDERDRAINS

	STATION	TO	STATION	MAINLINE SHOULDER REMOVAL AND REPLACEMENT 11" 60100076 (FEET)	PIPE UNDERDRAINS, 4" 60107600		MAINLINE PIPE UNDERDRAIN REMOVAL Z0040530 (FOOT)
					DRIVING LANE (FOOT)	PASSING LANE (FOOT)	
SB URBAN	77+50.00		84+50.00	699.0	699.0	0.0	699.0
SB URBAN	84+50.00		91+00.00	764.7	651.1	113.6	764.7
SB URBAN	91+00.00		96+00.00	1,006.9	500.1	506.7	1,006.9
SB URBAN	96+00.00		101+00.00	1,006.8	500.1	506.7	1,006.8
SB URBAN	101+00.00		106+00.00	1,006.7	500.1	506.7	1,006.7
SB URBAN	106+00.00		111+00.00	1,006.7	500.0	506.6	1,006.7
SB URBAN	111+00.00		116+00.00	1,006.3	500.0	506.3	1,006.3
SB URBAN	116+00.00		123+96.00	1,364.3	796.4	567.9	1,364.3
SB URBAN	126+00.00		131+00.00	1,000.1	500.0	500.1	1,000.1
SB URBAN	131+00.00		136+00.00	1,000.0	500.0	500.0	1,000.0
SB URBAN	136+00.00		141+00.00	1,000.0	500.0	500.0	1,000.0
SB URBAN	141+00.00		146+00.00	1,001.7	500.0	501.7	1,001.7
SB URBAN	146+00.00		151+00.00	1,001.1	500.0	501.1	1,001.1
SB URBAN	151+00.00		156+00.00	500.0	500.0	0.0	500.0
SB URBAN	151+00.00		157+00.00	613.7	0.0	613.7	613.7
SB URBAN	156+00.00		161+00.00	46.0	46.0	0.0	46.0
SB URBAN	157+00.00		161+00.00	400.0	0.0	400.0	400.0
TR 181D	13+30.00		22+93.00	963.0	963.0	0.0	963.0
TR 181D	8+94.00		13+30.00	435.7	435.7	0.0	435.7
SB URBAN	161+00.00		166+00.00	500.0	0.0	500.0	500.0
SB URBAN	166+00.00		171+00.00	796.9	296.8	500.0	796.9
SB URBAN	171+00.00		176+00.00	1,000.0	500.0	500.0	1,000.0
SB URBAN	176+00.00		181+00.00	1,000.0	500.0	500.0	1,000.0
SB URBAN	181+00.00		186+00.00	1,000.1	500.0	500.1	1,000.1
SB URBAN	186+00.00		190+90.00	979.9	490.0	489.9	979.9
SB URBAN	190+90.00		196+00.00	533.6	23.6	510.1	533.6
TR 181A	0+00.00		6+58.00	657.4	657.4	0.0	657.4
SB URBAN	196+00.00		198+61.67	349.3	87.6	261.7	349.3
SB RURAL	198+61.67		201+00.00	521.7	238.3	283.3	521.7
SB RURAL	201+00.00		206+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	206+00.00		211+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	211+00.00		216+00.00	1,000.4	500.3	500.1	1,000.4
SB RURAL	216+00.00		221+00.00	1,000.9	500.6	500.3	1,000.9
SB RURAL	221+00.00		224+70.00	740.0	370.0	370.0	740.0
SB RURAL	224+70.00		229+75.00	1,010.2	505.0	505.2	1,010.2
SB RURAL	229+75.00		235+23.00	1,093.4	547.8	545.6	1,093.4
SB URBAN TOTAL				22,639.8	12,146.9	10,492.9	22,639.8
SB URBAN ROUNDED				22,640.0	12,147.0	10,493.0	22,640.0
SB RURAL TOTAL				7,366.7	3,662.1	3,704.6	7,366.7
SB RURAL ROUNDED				7,370.0	3,670.0	3,710.0	7,370.0

STA EQ  
STA EQ

	STATION	EROSION CONTROL BLANKET 25100630 (SQ YD)	CONCRETE HEADWALLS FOR PIPE DRAINS 60100060 (EACH)	DRIVING LANE OUTLET	PASSING LANE OUTLET	PIPE UNDERDRAINS, 4" (SPECIAL) 60108100		CONCRETE HEADWALL REMOVAL SPECIAL X5012650 (EACH)	DRIVING LANE PIPE UNDERDRAIN REMOVAL Z0040530 (FOOT)	PASSING LANE PIPE UNDERDRAIN REMOVAL Z0040530 (FOOT)
				SHOULDER REMOVAL AND REPLACEMENT 11" 60100076 (FEET)	SHOULDER REMOVAL AND REPLACEMENT 11" 60100076 (FEET)	OUTSIDE LENGTH (FOOT)	INSIDE LENGTH (FOOT)			
SB URBAN	77+50.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SB URBAN	84+50.00	4.0	1.0	10.0	0.0	26.0	0.0	1.0	26.0	0.0
SB URBAN	91+00.00	4.0	1.0	10.0	0.0	23.3	0.0	1.0	22.1	0.0
SB URBAN	92+00.00	4.0	1.0	0.0	6.0	0.0	19.0	1.0	0.0	19.5
SB URBAN	96+00.00	8.0	2.0	10.0	6.0	20.0	18.8	2.0	20.4	23.8
SB URBAN	101+00.00	8.0	2.0	10.0	6.0	19.1	20.9	2.0	22.2	22.5
SB URBAN	106+00.00	8.0	2.0	10.0	6.0	18.8	19.2	2.0	22.0	21.5
SB URBAN	111+00.00	8.0	2.0	10.0	6.0	19.1	20.8	2.0	21.7	21.6
SB URBAN	116+00.00	8.0	2.0	10.0	6.0	19.6	17.8	2.0	24.9	18.4
SB URBAN	123+96.00	4.0	1.0	10.0	0.0	19.4	0.0	1.0	24.0	0.0
SB URBAN	131+00.00	8.0	2.0	10.0	6.0	20.5	16.8	2.0	20.6	18.2
SB URBAN	136+00.00	8.0	2.0	10.0	6.0	20.1	17.3	2.0	18.7	18.2
SB URBAN	141+00.00	8.0	2.0	10.0	6.0	19.9	15.1	2.0	18.7	18.5
SB URBAN	146+00.00	8.0	2.0	10.0	6.0	17.4	16.0	2.0	19.5	20.8
SB URBAN	151+00.00	8.0	2.0	10.0	6.0	19.7	16.7	2.0	22.1	17.9
SB URBAN	156+00.00	4.0	1.0	10.0	6.0	24.0	0.0	2.0	23.7	16.9
SB URBAN	157+00.00	4.0	1.0	0.0	6.0	0.0	16.4	0.0	0.0	0.0
SB URBAN	161+00.00	8.0	2.0	10.0	6.0	18.8	17.3	2.0	17.3	18.0
TR 181D	13+30.00	4.0	1.0	6.0	0.0	16.6	0.0	1.0	17.3	0.0
TR 181D	8+94.00	4.0	1.0	6.0	0.0	15.5	0.0	1.0	15.0	0.0
SB URBAN	166+00.00	4.0	1.0	0.0	6.0	0.0	16.7	1.0	0.0	18.0
SB URBAN	171+00.00	8.0	2.0	10.0	6.0	22.3	17.1	2.0	23.3	18.5
SB URBAN	176+00.00	8.0	2.0	10.0	6.0	25.3	21.2	2.0	21.5	18.7
SB URBAN	181+00.00	8.0	2.0	10.0	6.0	27.8	20.4	2.0	28.6	17.6
SB URBAN	186+00.00	8.0	2.0	10.0	6.0	27.9	16.9	2.0	26.5	17.4
SB URBAN	190+90.00	4.0	1.0	0.0	6.0	0.0	16.6	1.0	0.0	17.4
TR 181A	6+58.00	4.0	1.0	6.0	0.0	16.5	0.0	1.0	16.7	0.0
SB URBAN	196+00.00	8.0	2.0	10.0	6.0	16.4	17.5	2.0	16.7	18.3
SB RURAL	201+00.00	8.0	2.0	10.0	6.0	20.0	16.3	2.0	25.3	18.3
SB RURAL	206+00.00	8.0	2.0	10.0	6.0	22.7	16.2	2.0	27.2	19.3
SB RURAL	211+00.00	8.0	2.0	10.0	6.0	22.2	16.7	2.0	27.1	17.6
SB RURAL	216+00.00	8.0	2.0	10.0	6.0	20.1	17.4	2.0	23.5	17.3
SB RURAL	221+00.00	8.0	2.0	10.0	6.0	19.8	17.1	2.0	30.5	16.6
SB RURAL	224+70.00	8.0	2.0	10.0	6.0	19.9	17.0	2.0	31.0	16.3
SB RURAL	229+75.00	8.0	2.0	20.0	12.0	20.0	17.6	4.0	53.8	36.2
SB RURAL	235+23.00	8.0	2.0	10.0	6.0	21.2	22.0	2.0	28.9	19.7
SB URBAN TOTAL		172.0	43.0	218.0	126.0	474.3	358.6	43.0	489.5	381.7
SB URBAN ROUNDED		180.0	50.0	350.0		840.0		50.0	880.0	
SB RURAL TOTAL		64.0	16.0	90.0	54.0	165.9	140.3	18.0	247.3	161.3
SB RURAL ROUNDED		70.0	20.0	150.0		310.0		20.0	410.0	

### PIPE UNDERDRAINS SUMMARY

	EROSION CONTROL BLANKET 25100630 (SQ YD)	CONCRETE HEADWALLS FOR PIPE DRAINS 60100060 (EACH)	PIPE UNDERDRAINS, 4" 60107600 (FOOT)	PIPE UNDERDRAINS, 4" (SPECIAL) 60108100 (FOOT)
SB URBAN	180.0	50.0	22,640.0	840.0
SB RURAL	70.0	20.0	7,370.0	310.0
TOTAL	250.0	70.0	30,010.0	1,150.0

### REMOVAL SUMMARY

		SHOULDER REMOVAL AND REPLACEMENT 11" 60100076 (FEET)		CONCRETE HEADWALL REMOVAL SPECIAL X5012650 (EACH)	PIPE UNDERDRAIN REMOVAL Z0040530 (FOOT)	
		SUB-TOTAL	TOTAL	TOTAL	SUB-TOTAL	TOTAL
SB URBAN	MAINLINE	22,640.0	22,990.0	50.0	22,640.0	23,520.0
SB URBAN	OUTLETS	350.0			880.0	
SB RURAL	MAINLINE	7,370.0	7,520.0	20.0	7,370.0	7,780.0
SB RURAL	OUTLETS	150.0			410.0	
TOTAL		30,510.0		70.0	31,300.0	

FILE NAME =	USER NAME = hoganbj	DESIGNED -	REVISED -
et:\pwork\pwork\hoganbj\0339150\0570634-SHT-SCHEDULE.DGN		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2013	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: NA      SHEET NO. 11 OF 11 SHEETS      STA.      TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	57(2,3)RS(SB)	McLean	140	29
CONTRACT NO. 70634				
ILLINOIS FED. AID PROJECT				