

GENERAL NOTES

G.N.-663A

CALCIUM CHLORIDE SHALL BE APPLIED FULL WIDTH TO THE PROPOSED AGGREGATE ROADWAYS AND/OR DETOURS FOR THE SOLE PURPOSE OF CONTROLLING DUST. THIS WORK SHALL BE PERFORMED ON ALL FINAL SURFACES AS WELL AS ANY REMAINING AGGREGATE SURFACES THAT WOULD LAY OVER ANY PARTICULAR WEEKEND.

THE FOLLOWING APPLICATION RATE HAS BEEN USED TO CALCULATE THIS ESTIMATED QUANTITY: 5 LBS./SQ.YD.

ANY ADDITIONAL QUANTITY FOR MAINTENANCE WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 WHEN SPECIFIED BY THE ENGINEER.

G.N.-667

THE RESIDENT ENGINEER SHALL CONTACT THE PROGRAM DEVELOPMENT CHIEF OF SURVEYS PRIOR TO THE PRE-CONSTRUCTION CONFERENCE FOR INSTRUCTION AS TO SETTING OF TEMPORARY OR PERMANENT TIES FOR CENTERLINE ALIGNMENT CONTROL SURVEY MARKERS (PC, PT, AND PI). PROJECT IMPLEMENTATION PERSONNEL WILL BE RESPONSIBLE FOR LAYOUT OF THESE MARKERS.

G.N.-720 (SPECIAL)

CONTRACTOR SHALL REMOVE AND RELOCATE ALL EXISTING CH 50 ROADWAY AND TRAFFIC SIGNS WITHIN CONSTRUCTION LIMITS. CONTRACTOR SHALL COORDINATE WITH CHAMPAIGN COUNTY ENGINEERING DEPARTMENT (JEFF BLUE, PHONE 217-384-3800) REGARDING THE ADDITION OR REMOVAL OF SIGNAGE AS WELL AS THE LOCATION OF RELOCATED SIGNS. THIS WORK WILL NOT BE MEASURED FOR PAYMENT IN ACCORDANCE WITH ARTICLE 107.25 OF THE STANDARD SPECIFICATIONS.

ANY EXISTING SIGNS THAT ARE DAMAGED BY THE CONTRACTORS OPERATIONS DURING CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST.

G.N.-Z0038

AN ALUMINUM TABLET OF THE TYPE SHOWN ON STANDARD 667101 SHALL BE PLACED ON THE PROPOSED STRUCTURE AS DIRECTED BY THE ENGINEER. THE BENCH MARK ELEVATION WILL BE ESTABLISHED AND MARKED BY THE DEPARTMENT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR PERMANENT BENCH MARKS.

COMMITMENTS:

PARCEL 5761001TE & 5761002TE:

AS A RESULT OF ROW NEGOTIATIONS, PLEASE BE ADVISED OF THE FOLLOWING CHANGES:
KEN MORTON HAS REQUESTED THE FOLLOWING TREES AS REPLACEMENT TREES:

- (6) NORWAY SPRUCE (*picea abies*)
- (3) AUTUMN FANTASY MAPLE (*acer xfreemaniae* 'Autumn Fantasy')
- (3) BLACK HILL SPRUCE (*picea glauca* 'Densata')
- (2) KENTUCKY COFFEETREE-MAIL (*gymnocladus dioica*)
- (3) KATSURATREE (*cercidiphyllum japonicum*)
- (2) CHANTICLEER PEAR (*pyrus calleryana*)

MR. MORTON CAN BE REACHED AT HOME; 217-586-3517 OR HIS CELL; 217-778-2237 FOR REPLACEMENT OF THE TREES.

PARCEL 5761003TE:

AS A RESULT OF LAND ACQUISITION NEGOTIATIONS, THE PROPERTY OWNERS, MR. AND MRS. JIM PROUTY HAVE REQUESTED THREE (3) AUTUMN FANTASY MAPLE TREES (*Acer xfreemaniae* 'autumn fantasy') AND THREE (3) CHANTICLEER PEAR TREES (*pyrus calleryana*) FOR REPLACEMENT TREES. THE PROUTY'S WILL LOSE THE LARGE OAK TREE IN THEIR FRONT YARD DUE TO THE PROPOSED ROAD PROJECT AND HAVE REQUESTED THAT THE STUMP BE GROUND TO NO LESS THAN 18" BELOW FINAL GRADE.

MR. PROUTY CAN BE REACHED AT 841-3426 FOR PLACEMENT OF THE SIX TREES.

| | | | | | | | | | | | | | |
|--|-----------------------|-----------------|-----------|---|---------------------------|-------------------------|--------|--------------------|---------|--------|-----------------|--------------|----|
| FILE NAME | USER NAME = ceorlockm | DESIGNED - BMC | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | GENERAL NOTES | | | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| cr:\pvc\work\pwidot\ceorlockm\10200368\1070700-sht-undev.dgn | | DRAWN - BMC | REVISED - | | SCALE: N/A | SHEET NO. 2 OF 2 SHEETS | STA. - | TO STA. - | 74 | 10-4BR | CHAMPAIGN | 290 | 04 |
| | | CHECKED - | REVISED - | | | | | CONTRACT NO. 70700 | | | | | |
| | | DATE - 04-24-12 | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | | |