

## SCHEDULE OF QUANTITIES

RESURFACING QUANTITIES											
LOCATION	STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	COLD MIX AVG. THICKNESS (INCH)	40600100 BITUMINOUS MATERIALS PRIME COAT (GAL)	X4060205 COLD MIX ASPHALT MIXTURE (TON)	LR400300 BLOTTER AGGREGATE (TON)	
<b>PREPARATION OF BASE</b>											
<b>FILL AREAS</b>		VARIOUS SPOT LOCATIONS (10)				10.0	2.25			1.0	
<b>MAINLINE QUANTITIES</b>											
	372+12.50	TO	389+85.00	1,772.5	20.0	3,938.9	2.25	393.9	398.8	29.5	
	390+31.50	TO	425+66.30	3,534.8	20.0	7,855.1	2.25	785.5	795.3	58.9	
<b>SUB-TOTAL =</b>								<b>1,179.4</b>	<b>1,195.1</b>	<b>88.5</b>	
<b>INCIDENTAL QUANTITIES</b>											
<b>SIDEROAD</b>	373+52.24	RT		10.0	VARIES	107.1	1.875	10.7	9.0	0.8	
<b>SIDEROAD</b>	373+53.02	LT		10.0	VARIES	51.9	1.875	5.2	4.4	0.4	
<b>PE</b>	398+51.30	RT		10.0	VARIES	36.5	1.875	3.7	3.1	0.3	
<b>SUB-TOTAL =</b>								<b>19.6</b>	<b>16.5</b>	<b>1.5</b>	
<b>TOTAL =</b>								<b>1,199.0</b>	<b>1,211.6</b>	<b>89.9</b>	
<b>USE =</b>								<b>1,199.0</b>	<b>1,212.0</b>	<b>90.0</b>	