

SCHEDULE OF QUANTITIES

PAINT PAVEMENT MARKING - LINE 4" (78001110)				
WHITE -SOLID EDGE LINES				
STATION	TO	STATION	LOCATION	FEET
216+81.50		267+50.00	10.0' LT	5,068.5
216+81.50		267+50.00	10.0' RT	5,068.5
268+00.00		320+30.00	10.0' LT	5,230.0
268+00.00		320+30.00	10.0' RT	5,230.0
320+80.00		373+25.00	10.0' LT	5,245.0
320+80.00		372+88.00	10.0' RT	5,208.0
373+88.00		425+66.30	10.0' LT	5,178.3
374+16.00		425+66.30	10.0' RT	5,150.3
SUB-TOTAL =				41,378.6

YELLOW -SKIP DASH

STATION	TO	STATION	LOCATION	FEET
216+81.50		306+88.00	CL	2,251.6
307+94.00		425+66.30	CL	2,943.1
SUB-TOTAL =				5,194.7

YELLOW -SOLID (NO PASSING ZONES)

STATION	TO	STATION	DIRECTION	FEET
230+16.00	*	238+08.00	SB	792.0
243+89.00	*	250+23.00	NB	634.0
264+64.00	*	274+14.00	SB	950.0
274+67.00	*	285+76.00	NB	1,109.0
292+10.00	*	297+38.00	SB	528.0
302+13.00	*	307+94.00	NB	581.0
306+88.00	*	314+28.00	SB	740.0
317+45.00	*	325+90.00	NB	845.0
SUB-TOTAL =				6,179.0
TOTAL =				52,752.3
USE =				52,753.0

* STATIONS ARE APPROXIMATE

SURVEY MONUMENT COVER ASSEMBLY (Z0070100)		
STATION		EACH
373+52.24	CL	1.0
TOTAL =		1.0