

SCHEDULE OF QUANTITIES

78001110 PAINT PAVEMENT MARKING - LINE 4"					
WHITE -SOLID EDGE LINES					
STATION	TO	STATION	LOCATION		FEET
700+53.50		703+19.43	10.0' LT		265.9
700+53.50		703+19.43	10.0' RT		265.9
0+00.00		49+48.07	10.0' LT		4948.1
0+00.00		49+48.58	10.0' RT		4948.6
50+20.58		102+28.27	10.0' LT		5207.7
50+06.82		102+29.86	10.0' RT		5223.0
102+91.80		155+21.12	10.0' LT		5229.3
102+91.06		155+27.12	10.0' RT		5236.1
155+89.63		175+01.61	10.0' RT		1912.0
175+59.16		179+39.06	10.0' RT		379.9
180+05.72		183+75.98	10.0' RT		370.3
184+50.13		188+40.57	10.0' RT		390.4
189+07.86		192+86.05	10.0' RT		378.2
155+93.76		192+90.57	10.0' LT		3696.8
193+77.73		197+10.50	10.0' RT		332.8
193+70.44		197+16.38	10.0' LT		345.9
198+29.95		250+54.39	10.0' LT		5224.4
198+26.17		302+95.00	10.0' RT		10468.8
251+16.59		302+95.00	10.0' LT		5178.4
SUB-TOTAL =					54,824.2

YELLOW -SKIP DASH

STATION	TO	STATION	LOCATION		FEET
700+53.50		703+19.43	CL		66.5
0+00.00		163+37.47	CL		4,084.4
177+15.00		302+95.00	CL		3,145.0
SUB-TOTAL =					7,295.9

YELLOW -SOLID (NO PASSING ZONES)

STATION	TO	STATION	DIRECTION		FEET
163+37.47		172+16.00	EB		878.5
172+16.00		177+15.00	WB		499.0
SUB-TOTAL =					1,377.5
PROJECT TOTAL =					63,497.6
USE =					63,498.0

X0326219 BUMP REMOVAL

STATION	TO	STATION	DIRECTION	EACH
700+53.50		703+19.43	EB	6.0
0+00.00		302+95.00	EB	12.0
700+53.50		703+19.43	WB	3.0
0+00.00		302+95.00	WB	8.0
TOTAL =				29.0
USE =				29.0

NOTE:

* BUMP REMOVAL QUANTITIES MAY BE REVISED BY THE ENGINEER DURING CONSTRUCTION

Z0070100 SURVEY MONUMENT COVER ASSEMBLY

STATION		EACH
155+52.53	CL	1.0
TOTAL =		1.0
USE =		1.0