

SHOULDER RECONSTRUCTION

LOCATION	WIDTH	HOT-MIX ASPHALT BASE COURSE				HMA SURFACE COURSE, MIX "D", N90	AGG WEDGE SHOULDER TYPE B
		10 3/4" SQ YD	12" SQ YD	12 1/4" SQ YD	14 1/2" SQ YD	1 1/2" TON	TON
SN 054-0057, 054-0058							
PRE STAGE 1							
NB I-55 OUTSIDE SHOULDER							
STA 571+34.00 TO STA 576+09.90	8	423.02				35.53	30.11
STA 577+58.40 TO STA 581+84.00	8	378.31				31.78	26.93
SB I-55 OUTSIDE SHOULDER							
STA 571+84.50 TO STA 576+09.90	8			378.13		31.76	26.92
STA 577+58.40 TO STA 582+20.60	8			410.84		34.51	29.24
STAGE 1							
NB I-155 MEDIAN SHOULDER							
STA 574+96.00 TO STA 575+70.23	6	49.49				4.16	4.70
STA 577+98.07 TO STA 580+63.00	6	176.62				14.84	16.76
SB I-55 MEDIAN SHOULDER							
STA 574+68.00 TO STA 575+70.23	6			68.15		5.72	6.47
STA 577+98.07 TO STA 581+13.00	6			209.95		17.64	19.93
SN 054-0060, 054-0061							
PRE STAGE 1							
NB I-55 OUTSIDE SHOULDER							
STA 691+83.00 TO STA 696+58.77	10'	528.63				44.40	30.10
NB I-155 MEDIAN SHOULDER							
STA 692+31.00 TO STA 696+51.35	6'	280.23				23.54	26.60
STA 702+54.29 TO STA 706+09.00	6'	236.47				19.86	22.44
SB I-55 MEDIAN SHOULDER							
STA 694+02.00 TO STA 697+42.16	6'			226.77		19.05	21.52
STA 703+58.10 TO STA 707+80.00	6'			281.27		23.63	26.69
SB I-55 OUTSIDE SHOULDER							
STA 693+29.00 TO STA 698+23.81	8'			439.83		36.95	31.31
STA 706+45.00 TO STA 708+26.00	10' -19.7'			203.29		17.08	11.45
SB I-55 ENTRANCE RAMP							
LEFT SHOULDER							
STA 12+80.00 TO STA 14+31.90	4'			67.51		5.67	9.61
SN 054-0063, 054-0064							
PRE-STAGE 1							
NB OUTSIDE SHOULDER							
STA 276+23.00 TO STA 281+13.00	10'	544.44				45.73	31.00
STA 284+25.05 TO STA 288+45.00	10'	466.61				39.20	26.57
NB I-55 MEDIAN SHOULDER							
STA 277+55.00 TO STA 280+59.76	6'	203.17				17.07	19.28
STA 284+64.16 TO STA 287+15.00	6'	167.23				14.05	15.87
SB I-55 MEDIAN SHOULDER							
STA 277+65.00 TO STA 280+14.50	6'	166.33				13.97	15.79
STA 284+18.90 TO STA 287+25.00	6'	204.07				17.14	19.37
SB I-55 OUTSIDE SHOULDER							
STA 276+38.00 TO STA 280+53.60	11'			507.96		42.67	26.30
STA 283+66.00 TO STA 288+50.00	11'			591.56		49.69	30.62

CONTINUES NEXT COLUMN

SHOULDER RECONSTRUCTION

LOCATION	WIDTH	HOT-MIX ASPHALT BASE COURSE				HMA SURFACE COURSE, MIX "D", N90	AGG WEDGE SHOULDER TYPE B
		10 3/4" SQ YD	12" SQ YD	12 1/4" SQ YD	14 1/2" SQ YD	1 1/2" TON	TON
SN 054-0065, 0066, 0067, & 0068							
PRE-STAGE 1							
NB OUTSIDE SHOULDER							
STA 449+55.00 TO STA 456+39.00	10'	760.00				63.84	43.28
STA 457+57.50 TO STA 469+83.00	10'	1361.67				114.38	77.54
STA 471+34.20 TO STA 479+74.00	10'	933.11				78.38	53.14
STA 481+99.70 TO STA 486+65.00	VARY	417.22				35.05	29.44
STAGE 1							
SB OUTSIDE SHOULDER							
STA 447+05.00 TO STA 456+07.31	8'	802.05				67.37	57.09
STA 458+10.48 TO STA 468+07.50	8'	886.24				74.44	63.08
STA 468+07.50 TO STA 472+42.50	8'	386.67				32.48	27.52
STA 471+44.17 TO STA 475+32.00	10'	430.92				36.20	24.54
SN 054-0069							
CH 6							
LT STA 1043+00.00 TO STA 1048+46.80	10'					607.56	
LT STA 1052+09.51 TO STA 1057+00.00	10'					544.99	
RT STA 1043+00.00 TO STA 1047+90.45	10'					544.94	
RT STA 1051+53.25 TO STA 1057+00.00	10'					607.50	
TOTAL		9,802.50	2,304.99	2,285.74	1,099.52	1,107.78	901.21

AGGREGATE WEDGE SHOULDERS, TYPE B

LOCATION	TON
SN 054-0057, 054-0058	
PRE-STAGE 1	
NB MEDIAN SHOULDER	
STA 565+48.00 TO STA 569+26.00	151.25
STA 571+18.00 TO STA 574+96.00	151.25
SB MEDIAN SHOULDER	
STA 565+76.00 TO STA 569+54.00	151.25
STA 570+89.00 TO STA 574+68.00	151.65
SN 054-0065, 0066, 0067, & 0068	
STAGE 1	
SB MEDIAN SHOULDER	
STA 468+96.99 TO STA 471+44.17	98.90
STAGE 2	
NB OUTSIDE SHOULDER	
STA 469+33.64 TO STA 471+73.07	40.36
NB MEDIAN SHOULDER	
STA 469+33.64 TO STA 471+73.07	95.80
FINAL PHASE	
SB MEDIAN SHOULDER	
STA 443+36.78 TO STA 446+95.89	143.69
STA 448+41.90 TO STA 452+00.00	143.29
STA 472+00.00 TO STA 476+97.90	199.22
STA 484+03.00 TO STA 486+76.38	109.39
NB MEDIAN SHOULDER	
STA 443+27.18 TO STA 446+86.32	143.70
STA 448+40.63 TO STA 451+98.64	143.25
STA 478+99.93 TO STA 483+88.40	195.45
TOTAL	1,918.45

PCC RAMPED MEDIAN TERMINAL

LOCATION	EACH
CH 6 FINAL PHASE	
STA 1043+74.69 TO STA 1043+80.69	1
STA 1056+13.09 TO STA 1056+19.09	1
TOTAL	2

TEMPORARY RAMP

LOCATION	WIDTH	SQ YD
CH 6		
STAGE 1		
STA 1048+33.91 TO STA 1048+38.91	32.0'	17.78
STA 1051+75.34 TO STA 1051+80.34	24.5'	13.61
STAGE 2		
STA 1048+19.66 TO STA 1048+24.66	24.5'	13.61
STA 1051+61.10 TO STA 1051+66.10	32.0'	17.78
TOTAL		62.78



JOB = 2236.10
 FILE NAME = D672E11-shr-Schedules.dgn
 PLOT SCALE =
 PLOT DATE = 3/18/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 2 OF 19 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	45
CONTRACT NO. 72E11				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				