

REMOVE INLET BOX

LOCATION	EACH
SN 054-0060, 054-0061	
PRE STAGE 1	
NB I-55 OUTSIDE SHOULDER	
STA 696+63.00	1
SB I-55 OUTSIDE SHOULDER	
STA 698+05.00	1
STAGE 1	
NB I-55 MEDIAN SHOULDER	
STA 696+99.00	1
STA 702+44.00	1
SB I-55 MEDIAN SHOULDER	
STA 697+66.00	1
STA 703+18.00	1
STAGE 2	
NB OUTSIDE SHOULDER	
STA 701+91.00	1
SB OUTSIDE SHOULDER	
STA 703+47.00	1
SN 054-0065, 054-0066	
PRE STAGE 1	
SB I-55 OUTSIDE SHOULDER	
STA 456+35.00	1
STAGE 2	
NB MEDIAN SHOULDER	
STA 456+27.00	1
SN 054-0067, 054-0068	
STAGE 1	
SB I-55 OUTSIDE SHOULDER	
STA 471+11.00	1
STAGE 2	
NB MEDIAN SHOULDER	
STA 471+43.00	1
TOTAL	12

PIPE CULVERT REMOVAL

LOCATION	TYPE	FOOT
SN 054-0057 & 054-0058		
STA 569+49.00 TO STA 567+75.00	24" CMP	174
STA 569+00.00 TO STA 569+50.00	12" CMP	48
STA 569+50.00 TO STA 569+50.00	18" CMP	25
STA 569+50.00 TO STA 569+50.00	18" CMP	27
STA 569+05.00 TO STA 569+50.00	12" CMP	43
STA 571+74.00 TO STA 569+51.00	24" CMP	223
SN 054-0067		
STA 470+30.00 TO STA 471+35.00	48" CONC	105
TOTAL		645

PIPE DRAIN REMOVAL

LOCATION	FOOT
SN 054-0060, 054-0061	
PRE STAGE 1	
NB I-55 OUTSIDE SHOULDER	
STA 696+63.00	104
SB I-55 OUTSIDE SHOULDER	
STA 698+05.00	36
STAGE 1	
NB I-55 MEDIAN SHOULDER	
STA 696+99.00	24
STA 702+44.00	36
SB I-55 MEDIAN SHOULDER	
STA 697+66.00	24
STA 703+18.00	48
STAGE 2	
NB OUTSIDE SHOULDER	
STA 696+63.00	12
STA 701+91.00	112
SB OUTSIDE SHOULDER	
STA 698+05.00	12
STA 703+47.00	62
SN 054-0065, 054-0066	
PRE STAGE 1	
SB I-55 OUTSIDE SHOULDER	
STA 456+35.00	30
STAGE 2	
NB MEDIAN SHOULDER	
STA 456+27.00	18
SN 054-0067, 054-0068	
STAGE 1	
SB I-55 OUTSIDE SHOULDER	
STA 471+11.00	58
STAGE 2	
NB MEDIAN SHOULDER	
STA 471+43.00	110
TOTAL	686

BRIDGE APPROACH SHOULDER REMOVAL

LOCATION	WIDTH	SQ YD
SN 054-0060, 054-0061		
PRE STAGE 1		
NB I-55 OUTSIDE SHOULDER		
STA 696+58.77 TO STA 696+91.35	10'	31.62
SB I-55 OUTSIDE SHOULDER		
STA 698+00.93 TO STA 698+23.81	10'	17.02
STAGE 1		
NB I-55 MEDIAN SHOULDER		
STA 696+95.25 TO STA 697+18.54	6'	13.71
SB I-55 MEDIAN SHOULDER		
STA 697+60.73 TO STA 697+93.06	6'	17.02
SN 054-0065, 054-0066		
STAGE 1		
SB OUTSIDE SHOULDER		
STA 456+30.27 TO STA 456+50.73	10'	22.73
SN 054-0067, 054-0068		
STAGE 1		
SB OUTSIDE SHOULDER		
STA 470+94.42 TO STA 471+16.27	10'	24.28
SN 054-0065, 054-0066		
STAGE 2		
NB MEDIAN SHOULDER		
STA 456+21.80 TO STA 456+41.74	6'	13.29
SN 054-0067, 054-0068		
STAGE 2		
NB MEDIAN SHOULDER		
STA 471+25.90 TO STA 471+48.10	6'	14.80
TOTAL		154.47

HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"

LOCATION	SQ YD
SN 054-0057, 054-0058	
PRE-STAGE 1	
SB OUTSIDE SHOULDER	
STA 568+90.90 TO STA 571+84.50	326.22
NB OUTSIDE SHOULDER	
STA 568+73.00 TO STA 571+34.00	290.00
TOTAL	616.22



JOB = 2236.10  
 FILE NAME = D672E11-shr-Schedules.dgn  
 PLOT SCALE = 1:8333 1/4 IN.  
 PLOT DATE = 3/18/2013

DESIGNED - NAK  
 DRAWN - SJS  
 CHECKED - NAK  
 DATE - 1/4/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 9 OF 19 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	52
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72E11	