

STEEL CASINGS 18"

LOCATION	STEEL CASING	TRENCH BACKFILL
	FOOT	CU YD
STA 470+56.00	407	180
TOTAL	407	180

PIPE UNDERDRAIN OUTLET EXTENSION FOR 4" PIPE

LOCATION	EACH
SN 054-0065, 0066 ,0067, & 0068	
PRE-STAGE 1	1
LT STA 445+78	1
LT STA 475+98	1
LT STA 486+00	1
RT STA 445+78	1
RT STA 480+98	1
TOTAL	6

REMOVE AND REPLACE INLET BOX 610001 GRATES

LOCATION	EACH
SN 054-0069	
PRE-STAGE 1	
EB CH 6	
STA 1047+96.00	3
STA 1051+47.00	3
WB CH 6	
STA 1048+53.00	3
STA 10+52.04	3
TOTAL	12

REMOVE AND REINSTALL INLET BOX

LOCATION	EACH
SN 054-0065, 0066 ,0067, & 0068	
PRE-STAGE 1	
STA 446+38.00	1
TOTAL	1

END SECTIONS 24"

LOCATION	EACH
SN 054-0065, 0066 ,0067, & 0068	
PRE-STAGE 1	1
STA 476+51.55	1
STA 480+23.20	1
STA 482+00.40	1
STA 485+24.60	
TOTAL	4

SHOULDER INLETS

LOCATION	INLET BOX STANDARD 609006		INLET BOX STANDARD 610001	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID EACH	PIPE DRAINS 12" FOOT	END SECTIONS 12" EACH	LENGTH OF RIPRAP SWALE FOOT	STONE RIPRAP, CLASS A4 TON	FILTER FABRIC SQ YD
	TYPE C EACH	TYPE D EACH	TYPE F EACH						
SN 054-0060 & SN 054-0061									
STAGE 1									
NB I-55 MEDIAN									
STA 696+61.20	1			1	68	1			
STA 702+46.80	1			1	38	1			
SB I-55 MEDIAN									
STA 697+49.70	1			1	36	1			
STA 703+25.80	1			1	58	1			
STAGE 2									
NB I-55 OUTSIDE									
STA 696+41.30		1			4	1	97	71.83	129.33
STA 702+15.30		1			4	1	92	68.13	122.67
SB I-55 OUTSIDE									
STA 697+63.70		1			4	1	46	34.07	61.33
STA 703+43.00							100	45.00	66.67
STA 703+66.10		1			4	1	88	65.17	117.33
SN 054-0065 THRU SN 054-0068									
STAGE 1									
SB I-55 OUTSIDE									
STA 456+14.00		1			4	1	66	48.88	88.00
STA 458+17.00			1		4	1	67	49.62	89.33
STA 461+00.00			1		4	1	67	49.62	89.33
STA 464+00.00			1		4	1	67	49.62	89.33
STA 467+00.00			1		4	1	67	49.62	89.33
STA 472+25.00			1		4	1	67	49.62	89.33
STAGE 2									
NB I-55 MEDIAN									
STA 456+06.00		1			4	1	32	23.70	42.67
TOTAL	4	6	5	4	244	15	856	604.88	1074.65

THE CONTRACTOR SHALL VERIFY PIPE DRAIN LENGTHS PRIOR TO ORDERING MATERIALS

TEMPORARY DRAINAGE STRUCTURES

LOCATION	MANHOLES, TYPE A, 4'-DIAMETER		MH, TY A, 5' DIA	INLETS, TYPE B
	TYPE 1 FRAME, CLOSED LID	WITH MEDIAN INLET (604106)	WITH MEDIAN INLET (604106)	WITH MEDIAN INLET (604106)
	EACH	EACH	EACH	EACH
SN 054-0065, 0066 ,0067, & 0068				
PRE-STAGE 1				
STA 446+27.10 0.55' LT	1			
STA 446+47.26 0.70' LT		1		
STA 447+66.40 22.2' RT			1	
STA 447+66.40 22.6' LT				1
STA 449+00.00 CENTERLINE		1		
TOTAL	1	2	1	1

PIPE CULVERTS, CLASS D, TYPE 1 (TEMPORARY)

LOCATION	PIPE CULVERTS CLASS D		TRENCH BACKFILL
	TYPE 1 18" FOOT	TYPE 1, 24" FOOT	CU YD
	SN 054-0065, 0066 ,0067, & 0068		
PRE-STAGE 1			
STA. 446+27.10 0.55' LT TO STA. 446+47.26 0.70' LT		19	
STA. 446+47.26 0.70' LT TO STA. 447+66.00 22.2' RT		119	11.5
STA. 447+66.00 22.6' LT TO STA. 447+66.00 22.2' RT	43		3.9
STA. 447+66.01 22.2' RT TO STA. 449+00.00 CENTERLINE		133	18.6
STA 476+57.55 TO STA 480+17.20		360	10.4
STA 482+06.40 TO STA 485+18.60		312	4.3
TOTAL	43	943	48.7



JOB = 2236.10
 FILE NAME = D672E11-sht-Schedules.dgn
 PLOT SCALE = 1/8333 "/>

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 11 OF 19 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	54
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72E11	