

GUARDRAIL AND BARRIER WALL MARKERS

LOCATION	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED
	EACH	EACH	EACH	EACH
SN 054-0057, 054-0058				
FINAL PHASE				
NB I-55 OUTSIDE SHOULDER				
STA 574+64.25 TO STA 575+94.90	2			
STA 575+94.90 TO STA 577+73.40		3	3	
STA 577+73.40 TO STA 579+00.55	2			
NB I-55 MEDIAN SHOULDER				
STA 571+78.25 TO STA 575+94.90	5			1
STA 575+94.90 TO STA 577+73.38		3	3	
SB I-55 MEDIAN SHOULDER				
STA 575+94.90 TO STA 577+73.40		3	3	
STA 577+73.40 TO STA 579+04.05	2			
SB I-55 OUTSIDE SHOULDER				
STA 574+67.75 TO STA 575+94.90	2			
STA 575+94.90 TO STA 577+73.40		3	3	
STA 577+73.40 TO STA 579+04.05	2			
SN 054-0060, 054-0061				
FINAL PHASE				
NB I-55 OUTSIDE SHOULDER				
STA 695+45.99 TO STA 696+64.14	2			
STA 696+64.14 TO STA 701+85.02		7	7	
STA 701+85.02 TO STA 703+49.53	3			
NB I-55 MEDIAN SHOULDER				
STA 695+50.25 TO STA 696+93.40	2			
STA 696+93.40 TO STA 702+34.10		7	7	
SB I-55 MEDIAN SHOULDER				
STA 697+64.75 TO STA 703+02.95		7	7	
STA 703+02.95 TO STA 704+71.10	3			
SB I-55 OUTSIDE SHOULDER				
STA 696+41.58 TO STA 698+06.26	3			
STA 698+06.26 TO STA 703+43.26		7	7	
STA 703+43.26 TO STA 704+61.42	2			
SB BL 55				
STA 47+25.02 TO STA 50+87.50	4			1
NB BL 55				
STA 49+08.75 TO STA 52+71.24	4			1
SN 054-0063, 054-0064				
FINAL PHASE				
NB I-55 OUTSIDE SHOULDER				
STA 279+55.35 TO STA 280+98.50	2			
TO STA 280+98.50 TO STA 284+43.20		5	5	
NB I-55 MEDIAN SHOULDER				
STA 279+51.70 TO STA 280+82.34	2			
STA 280+82.34 TO STA 284+27.00		5	5	

CONTINUES NEXT COLUMN

GUARDRAIL AND BARRIER WALL MARKERS

LOCATION	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED
	EACH	EACH	EACH	EACH
SB I-55 MEDIAN SHOULDER				
STA 280+51.65 TO STA 283+96.30		5	5	
STA 283+96.30 TO STA 285+26.95	2			
SB I-55 OUTSIDE SHOULDER				
STA 280+35.50 TO STA 283+80.16		5	5	
STA 283+80.16 TO STA 285+23.35	2			
SN 054-0065, 054-0066				
NB I-55 OUTSIDE SHOULDER				
STA 454+98.45 TO STA 456+38.70	2			
STA 456+38.70 TO STA 457+56.05		2	2	
STA 457+56.05 TO STA 459+05.25	2			
NB I-55 MEDIAN SHOULDER				
STA 455+00.15 TO STA 456+41.90	2			
STA 456+41.90 TO STA 457+60.55		2	2	
SB I-55 MEDIAN SHOULDER				
STA 456+47.50 TO STA 457+67.15		2	2	
STA 457+67.15 TO STA 459+11.70	2			
SB I-55 OUTSIDE SHOULDER				
STA 456+50.90 TO STA 457+71.85		2	2	
STA 457+71.85 TO STA 459+18.00	2			
SN 054-0067, 054-0068				
NB I-55 OUTSIDE SHOULDER				
STA 468+30.35 TO STA 472+71.35	6			
SB I-55 OUTSIDE SHOULDER				
STA 467+87.96 TO STA 473+49.43	8			
TOTAL	70	68	68	3

GUARDRAIL REMOVAL

LOCATION	FOOT
SN 054-0067, 054-0068	
STAGE 1	
SB OUTSIDE	
STA 457+79.00 TO STA 469+22.70	1143.7
STA 471+06.15 TO STA 472+43.90	137.8
SB MEDIAN	
STA 471+17.00 TO STA 473+01.00	182.3
STAGE 2	
NB OUTSIDE	
STA 469+57.65 TO STA 469+72.05	15.0
STA 471+47.45 TO STA 471+90.40	43.0
NB MEDIAN	
STA 467+00.40 TO STA 469+69.10	271.4
TOTAL	1,793.2



JOB = 2236.10
 FILE NAME = D672E11-sht-Schedules.dgn
 PLOT SCALE = 1/8333 "/>

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 13 OF 16 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	56
CONTRACT NO. 72E11				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				