

TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
SN 054-0057, 045-0058	
STAGE 1	
NB I-55	
STA 572+15.50 TO STA 574+40.50 12:1 TAPER	225.0
STA 574+40.50 TO STA 579+28.00 TANGENT	487.5
SB I-55	
STA 574+40.50 TO STA 579+28.00 TANGENT	487.5
STA 579+28.00 TO STA 581+53.00 12:1 TAPER	225.0
SN 054-0060, 054-0061	
STAGE 1	
NB I-55	
STA 692+88.85 TO STA 695+26.35 12:1 TAPER	237.5
STA 695+26.35 TO STA 703+63.85 TANGENT	837.5
SB I-55	
STA 696+47.25 TO STA 704+84.75 TANGENT	837.5
STA 704+84.75 TO STA 707+22.25 12:1 TAPER	237.5
SN 054-0063, 054-0064	
STAGE 1	
NB I-55	
STA 277+09.40 TO STA 279+34.40 12:1 TAPER	225.0
STA 279+34.40 TO STA 285+84.40 TANGENT	650.0
SB I-55	
STA 278+94.26 TO STA 285+44.26 TANGENT	650.0
STA 285+44.26 TO STA 287+69.26 12:1 TAPER	225.0
SN 054-0065, 054-0066, 054-0067, 054-0068	
STAGE 1	
NB I-55	
STA 448+52.00 TO STA 482+98.00 TANGENT	3,487.5
TOTAL	8,812.5

TEMPORARY MODULAR GLARE SCREEN

LOCATION	FOOT
STA 475+00.00 TO STA 481+00.00	600
TOTAL	600

RELOCATE MODULAR GLARE SCREEN SYSTEM

LOCATION	FOOT
STA 449+50.00 TO STA 455+50.00	600
TOTAL	600

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
SN 054-0057, 045-0058	
STAGE 2	
NB I-55	
STA 572+53.00 TO STA 574+40.50 12:1 TAPER	187.5
STA 574+40.50 TO STA 579+28.00 TANGENT	487.5
SB I-55	
STA 574+40.50 TO STA 579+28.00 TANGENT	487.5
STA 579+28.00 TO STA 581+15.50 12:1 TAPER	187.5
SN 054-0060, 054-0061	
STAGE 2	
NB I-55	
STA 693+51.35 TO STA 695+26.35 12:1 TAPER	175.0
STA 695+26.35 TO STA 703+63.85 TANGENT	837.5
SB I-55	
STA 696+47.25 TO STA 704+84.75 TANGENT	837.5
STA 704+84.75 TO STA 706+84.05 12:1 TAPER	200.0
STA 706+84.05 TO STA 707+80.25 4:1 TAPER	100.0
SN 054-0063, 054-0064	
STAGE 2	
NB I-55	
STA 277+59.40 TO STA 279+34.40 12:1 TAPER	175.0
STA 279+34.40 TO STA 285+84.40 TANGENT	650.0
SB I-55	
STA 278+94.26 TO STA 285+44.26 TANGENT	650.0
STA 285+44.26 TO STA 287+19.26 12:1 TAPER	175.0
SN 054-0065, 054-0066, 054-0067, 054-0068	
STAGE 2	
SB I-55	
STA 447+98.40 TO STA 476+55.55 TANGENT	2,862.5
TOTAL	8,012.5

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	EACH
SN 054-0057, 054-0058	
STAGE 1	
NB I-55	
STA 572+15.50	1
SB I-55	
STA 581+53.00	1
SN 054-0060, 054-0061	
STAGE 1	
NB I-55	
STA 692+88.85	1
SB I-55	
STA 707+22.25	1
SN 054-0063, 054-0064	
STAGE 1	
NB I-55	
STA 277+09.40	1
SB I-55	
STA 287+69.26	1
SN 054-0065, 054-0066, 054-0067, 054-0068	
STAGE 1	
NB I-55	
STA 448+52.00	1
TOTAL	7

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	EACH
SN 054-0057, 054-0058	
STAGE 2	
NB I-55	
STA 572+53.00	1
SB I-55	
STA 581+15.50	1
SN 054-0060, 054-0061	
STAGE 2	
NB I-55	
STA 693+51.35	1
SB I-55	
STA 707+80.25	1
SN 054-0063, 054-0064	
STAGE 2	
NB I-55	
STA 277+59.40	1
SB I-55	
STA 287+19.26	1
SN 054-0065, 054-0066, 054-0067, 054-0068	
STAGE 2	
NB I-55	
TO STA 476+55.55	1
TOTAL	7



JOB = 2236.10
 FILE NAME = D672E11-sht-Schedules.dgn
 PLOT SCALE = 1/8333 "/>

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 14 OF 19 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	57
CONTRACT NO. 72E11			ILLINOIS FED. AID PROJECT	